

COMPOSITE QUANTITY SHEET 1

			COVENTRY-NEWPORT STP 2308 (I)				COVENTRY AV-FY13-001	TOTALS		DESCRIPTIONS				
			ROADWAY (STATE ROUTE)	EROSION CONTROL	BRIDGE ITEMS	FULL C.E.	ROADWAY (CLASS I T.H.)	AIRPORT	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NO.	ROUND
			150						150		CY	EARTH BORROW	203.30	-
			80						80		CY	TRENCH EXCAVATION OF EARTH	204.20	-
			20						20		CY	TRENCH EXCAVATION OF ROCK	204.21	-
											CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	-
			40075				1125		41200		SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10	-
			1704				6		1710		TON	SUBBASE OF CRUSHED GRAVEL, FINE GRADED	301.28	-
			4230				120		4350		TON	SUBBASE, RAP	301.40	-
			41800				700	21300	63800		SY	RECLAIMED STABILIZED BASE	310.20	-
			1435				35		1470		TON	AGGREGATE SHOULDERS	402.12	-
											LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50	-
			5210				90		5300		CWT	EMULSIFIED ASPHALT, COLD MIX	415.25	-
			11130				370		11500		TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT	490.30	-
									2		LU	AIR VOIDS PAY ADJUSTMENT (N.A.B.I.)	490.31	-
											LU	MAT DENSITY PAY ADJUSTMENT (N.A.B.I.)	490.32	-
											LU	SURFACE TOLERANCE PAY ADJUSTMENT (N.A.B.I.)	490.33	-
											LU	LONGITUDINAL JOINT COMPACTION PAY ADJUSTMENT (N.A.B.I.)	490.34	-
					70				70		LF	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG	516.10	-
					300				300		LF	REMOVAL OF EXISTING RAILING	525.10	-
					300				300		LF	BRIDGE RAILING REPAIR, TYPE I	525.50	-
					100				100		CF	RAPID SETTING CONCRETE REPAIR MATERIAL WITH COARSE AGGREGATE	580.20	-
			340						340		LF	6 INCH UNDERDRAIN PIPE	605.10	-
			20						20		LF	6 INCH UNDERDRAIN CARRIER PIPE	605.20	-
			19						20		HR	POWER GRADER RENTAL	608.15	-
			136				4		140		HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	-
			14						15		HR	POWER BROOM RENTAL, TYPE I	608.30	-
			160				5		165		HR	TRUCK RENTAL	608.37	-
			14						15		HR	LOADER RENTAL, TYPE I	608.40	-
				570					570		CY	STONE FILL, TYPE I	613.10	-
			7						8		EACH	RELOCATE MAILBOX, SINGLE SUPPORT	617.10	-
			30						30		EACH	YIELDING MARKER POSTS	619.17	-
			925						925		LF	STEEL BEAM GUARDRAIL, GALVANIZED	621.20	-
			550						550		LF	STEEL BEAM GUARDRAIL, GALVANIZED W/8 FEET POSTS	621.205	-
			150						150		LF	HD STEEL BEAM GUARDRAIL, GALVANIZED	621.21	-
			6						6		EACH	ANCHOR FOR STEEL BEAM RAIL	621.60	-
			1200						1200		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80	-
			510						510		HR	UNIFORMED TRAFFIC OFFICERS	630.10	-
			2250						2250		HR	FLAGGERS	630.15	-

PROJECT NAME: COVENTRY-NEWPORT CITY/COVENTRY
PROJECT NUMBER: STP 2308(I), AV-FY13-001
FILE NAME: p10c052.dgn PLOT DATE: 24-MAY-2012
PROJECT LEADER: JLL DRAWN BY: STANTEC
DESIGNED BY: STANTEC CHECKED BY: STANTEC
IPARM FILE: p01c052cqs01.i SHEET 2 OF 107