STATE OF VERMONT
AGENCY OF TRANSPORTATION

QUANTITY SHEET 1

VAOT Metric

SUMMARY OF ESTIMATED QUANTITIES

					BRIDGE	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NUMBER	RND
						5	5	EA	THINNING AND TRIMMING FOR SIGNS	201.31	EST
						40	40	m3	EARTH BORROW	203.30	EST
						290	290	m	SHOULDER BERM REMOVAL	203.99	4
						1	1	m3	TRENCH EXCAVATION OF EARTH (NOT A BID ITEM)	204.20	EST
						60 300	60 300	m2	COLD PLANING BIT. PAVEMENT	210.10	611
						165	165	t	SUBBASE OF CRUSHED GRAVEL (FINE GRADED)	301.28	EST
						60	60	t	AGGREGATE SHOULDERS (MOD)	402.12	EST
						13 810	13 810	kg	EMULSIFIED ASPHALT	404.65	140
						7260	7260	t	BITUMINOUS CONCRETE PAVEMENT (PG 64-28)	406.25	70
						1	1	LU	PRICE ADJUSTMENT ASPHALT CEMENT (NOT A BID ITEM)	406.50	-
					40		40	m	BRIDGE EXPANSION JOINT	516.10	1
						71	71	EA	CHANGING ELEV. OF DROP INLETS, CATCH BASINS OR MANHOLES	604.40	EST
						76	76	EA	REHABING OF DI CB OR MH, CLASS I	604.412	EST
						47	47	EA	CHANGING ELEVATION OF SEWER MANHOLE	604.42	EST
						10	10	HR	POWER GRADER RENTAL	608.15	EST
						1	1	HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	EST
						70	70	HR	POWER BROOM RENTAL, TYPE II	608.31	EST
						1	1	HR	TRUCK RENTAL	608.37	EST
						1	1	HR	LOADER RENTAL, TYPE I	608.40	EST
						7530	7530	m3	DUST CONTROL WITH WATER	609.10	77
						65	65	m	STEEL BEAM GUARDRAIL	621.20	4
						2	2	EA	ANCHOR FOR STEEL BEAM RAIL	621.60	0
						20	20	EA	REPLACE GUARDRAIL POST ASSEMBLY	621.76	EST
						10	10	EA	REPLACE GUARDRAIL BEAM UNIT	621.77	EST
						60	60	m	REMOVL AND DISP OF GUARDRAIL	621.80	0
						117	117	EA	ADJUST ELEVATION OF VALVE BOX	629.20	0
						670	670	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST
						3500	3500	HR	FLAGGERS	630.15	EST
						1	1	LS	FIELD OFFICE - ENGINEERS	631.10	-
						1	1	LS	TESTING EQUIPMENT - CONCRETE	631.16	-

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		AGGREGATE SHOULDERS (MOD)
45	t	VT ROUTE 9
10	t	GUARDRAIL TERMINALS
55	t	SUBTOTAL
5	t	ROUNDING
60	t	TOTAL
		BITUMINOUS CONCRETE PAVEMENT (PG 64-28)
4783	t	VT ROUTE 9, TYPE III, WEARING COURSE
2052	t	VT ROUTE 9, TYPE IV, LEVELING COURSE
338	t	SIDEROADS
17	t	DRIVES
7190	t	SUBTOTAL
70	t	ROUNDING
7260	t	TOTAL

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT NAME: BRATTLEBORO

PROJECT NUMBER: ST-STP 2303(I)S

FILE NAME: /PAVE/0ID026/PD026.DGN
PROJECT LEADER: WRH
DESIGNED BY:
pd026qsl.1

PLOT DATE: 10-JUL-2007 07:2
DRAWN BY: JAC
CHECKED BY: NLL
SHEET 4 OF 55