STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 1

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	49 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	TUBULAR STEEL Ø (mm) FOUND-ATION	kg/m 75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																									
STA 6+832 RT BRATTLEBORO	BIKE LANE AHEAD	1	610	764	0.47						1			14′																						
RETAIN ~~STA 6+911 LT~~ EXISTING	WEST	1	600	300	0.18						~~1~~			~~X~~		~~X~~																				E-136BM
	VERMONT 9	1	600	600	0.36																														E-136BM
STA 7+038 LT	MEADOW BROOK RD	1					1				1			X		~~X~~																		SALVAGED SIGN TO BE INSTALLED USING TOP MOUNTING BRACKET, MOUNTED PERPENDICULAR TO TOP OF STREET SIGN		
	WESTERN AVE	1					1							13′																				SALVAGED SIGN TO BE INSTALLED USING TOP MOUNTING BRACKET, MOUNTED 0.3M FROM AND PERPENDICULAR TO TOP OF STOP SIGN		
	STOP 0090 1302 0443	1 1	750	750	0.56		 1																											BACK TO BACK		E-143M
STA 6+912 LT	BIKE LANE ENDS	1	610	764	0.47						1			14′																						
STA 7+122 RT	STOP RIGHT LANE BIKES ONLY	1 1	750 600	750 750	0.56 0.45						1			X 13′		~~X~~																		BACK TO BACK		E-143M E-144M
		1 1	450 450	450 450	0.20 0.20																													BACK TO BACK		E-150M
STA 7+010 RT	RIGHT LANE BIKES ONLY	1	610	764	0.47						1			13′																						
STA 7+122 RT		1	600	750	0.45						1			X 13′		~~X~~																				E-144M
		1 1	450 450	450 450	0.20 0.20																													BACK TO BACK		E-150M
STA 7+131 RT	STOCKWELL DR	1					1				1			X 12.5′		~~X~~																		SALVAGED SIGN TO BE INSTALLED USING TOP MOUNTING BRACKET, MOUNTED PERPENDICULAR TO TOP OF STREET SIGN		
	WESTERN AVE	1					1																											SALVAGED SIGN TO BE INSTALLED USING TOP MOUNTING BRACKET, MOUNTED 0.3M FROM AND PERPENDICULAR TO TOP OF STOP SIGN		
	STOP 0090 1302 0443	1 1	750	750	0.56		 1																											BACK TO BACK		E-143M
STA 7+168 RT	RIGHT LANE BIKES ONLY	1	610	764	0.47						1			13′																						
												m	m	m	m	m	m		EA	kg	kg	kg		kg	kg	kg	kg								
														~~23.0~~		23.0																				
														105.5′		32.16																				
					5.26	FUR 12-21-04 DAN TYLER																																
TOTALS			m²	m²	~~3.92~~		EA. 6	m²				~~m~~		~~23.0~~		m 23.0					kg		EA.		kg				EA.	EA.	kg					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: BRATTLEBORO
PROJECT NUMBER: ST-STP 2303(I)S

FILE NAME: /PAVE/OID026/PD026.dgn
PROJECT LEADER: WRH
DESIGNED BY: -
CLD REF. NO.: pd026tssl.1
PLOT DATE: $DATE$
DRAWN BY: JAC
CHECKED BY: NLL
SHEET 35 OF 55