STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 2

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	49 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	TUBULAR STEEL Ø (mm) FOUNDATION	kg/m 75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																								
STA 7+399 LT	GARFIELD DR	1					1				1			X 13′		X																	SALVAGED SIGN TO BE INSTALLED USING TOP MOUNTING BRACKET, MOUNTED PERPENDICULAR TO TOP OF STREET SIGN		
	WESTERN AVE	1					1																										SALVAGED SIGN TO BE INSTALLED USING TOP MOUNTING BRACKET, MOUNTED 0.3M FROM AND PERPENDICULAR TO TOP OF STOP SIGN		
	STOP	1	750	750	0.56																													E-143M
STA 7+290 LT	RIGHT LANE BIKE ONLY	1	610	764	0.47						1			16′																				
~~RETAIN STA 7+421 LT~~ EXISTING	~~WEST~~	1	600	300	0.18						1			X		X																		E-136BM
	~~VERMONT 9~~	1	600	600	0.36																													E-136BM
STA 7+450 RT		1	750	750	0.56						1			X 14′		X																	FLUORESCENT YELLOW-GREEN SHEETING		E-152M
		1	600	300	0.18																												FLUORESCENT YELLOW-GREEN SHEETING	53	
STA 7+407 RT	BIKE LANE ENDS	1	610	764	0.47						1			12.5′																				
STA 7+453 LT		1	750	750	0.56						1			X 14′		X																	FLUORESCENT YELLOW-GREEN SHEETING		E-152M
		1	600	300	0.18																												FLUORESCENT YELLOW-GREEN SHEETING	53	
STA 7+522 RT	GREENLEAF ST	1					1				1			X 13′		X																	SALVAGED SIGN TO BE INSTALLED USING TOP MOUNTING BRACKET, MOUNTED PERPENDICULAR TO TOP OF STREET SIGN		
	WESTERN AVE	1					1																										SALVAGED SIGN TO BE INSTALLED USING TOP MOUNTING BRACKET, MOUNTED 0.3M FROM AND PERPENDICULAR TO TOP OF STOP SIGN		
	STOP	1	750	750	0.56																													E-143M
STA 7+489 LT	BIKE LANE AHEAD	1	610	764	0.47						1			14′																				
STA 7+525 RT		1	750	750	0.56						1			X 14′		X																	FLUORESCENT YELLOW-GREEN SHEETING		E-152M
		1	600	300	0.18																												FLUORESCENT YELLOW-GREEN SHEETING	53	
TOTALS					~~3.88~~ m²		4 EA.	4.75 m²				110.5′ m		~~27.6~~ 33.68		~~27.6~~ m																				

FUR 12-21-04 DAN TYLER

m m m m m m EA kg kg kg kg kg kg kg

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: BRATTLEBORO
PROJECT NUMBER: ST-STP 2303(I)S

FILE NAME: /PAVE/OID026/PD026.dgn
PROJECT LEADER: WRH
DESIGNED BY: -
CLD REF. NO.: pd026tss2.I

PLOT DATE: $DATE$
DRAWN BY: JAC
CHECKED BY: NLL
SHEET 36 OF 55