STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 3

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	FLANGED CHANNEL kg/m 3.0	FLANGED CHANNEL kg/m 4.5	SQUARE STEEL (mm) kg/m 44	SQUARE STEEL (mm) kg/m 49	SQUARE STEEL (mm) kg/m 63	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75	TUBULAR ALUMINUM Ø (mm) kg/m 100	TUBULAR ALUMINUM Ø (mm) kg/m 100 MOD	TUBULAR STEEL Ø (mm) FOUNDATION	TUBULAR STEEL Ø (mm) kg/m 75	TUBULAR STEEL Ø (mm) kg/m 89	TUBULAR STEEL Ø (mm) kg/m 100	TUBULAR STEEL Ø (mm) kg/m 125	W-SHAPE STEEL FTG. SIZE 600 mm	W-SHAPE STEEL FTG. SIZE 750 mm	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
														OPTION ITEMS																							
STA 7+527 LT		1	750	750	0.56						1			X 14′		X																	FLUORESCENT YELLOW-GREEN SHEETING		E-152M
		1	600	300	0.18																											FLUORESCENT YELLOW-GREEN SHEETING	53	
~~RETAIN STA 7+577 LT EXISTING~~		~~1~~	~~750~~	~~750~~	~~0.56~~						~~1~~			~~X~~		~~X~~																		E-145AM
STA 7+603 RT	BIKE LANE AHEAD	1	610	764	0.47						1			13′																				
STA 7+685 RT		1	750	750	0.56						1			X 14′		X																	FLUORESCENT YELLOW-GREEN SHEETING		E-152M
		1	600	300	0.18																											FLUORESCENT YELLOW-GREEN SHEETING	53	
STA 7+693 LT		1	750	750	0.56						1			X 14′		X																	FLUORESCENT YELLOW-GREEN SHEETING		E-152M
		1	600	300	0.18																											FLUORESCENT YELLOW-GREEN SHEETING	53	
STA 7+715 RT	RIGHT LANE BIKE ONLY	1	610	764	0.47						1			13′																				
STA 7+761 LT	GLEN ST	1					1				1			X 13′		X																	SALVAGED SIGN TO BE INSTALLED USING TOP MOUNTING BRACKET, MOUNTED 0.3M FROM AND PERPENDICULAR TO TOP OF STOP SIGN		
	STOP 0090 1302 0482	1 1	750	750	0.56		1																									BACK TO BACK		E-143M
STA 7+768 RT		1	750	750	0.56						1			X 14′		X																	FLUORESCENT YELLOW-GREEN SHEETING		E-152M
		1	600	300	0.18																											FLUORESCENT YELLOW-GREEN SHEETING	53	
STA 7+745 LT	BIKE LANE ENDS	1	610	764	0.47						1			13′																				
STA 7+768 RT	BONNYVALE RD	1					1				1			X 13′		X																	SALVAGED SIGN TO BE INSTALLED USING TOP MOUNTING BRACKET, MOUNTED PERPENDICULAR TO TOP OF STREET SIGN		
	WESTERN AVE	1					1																									SALVAGED SIGN TO BE INSTALLED USING TOP MOUNTING BRACKET, MOUNTED 0.3M FROM AND PERPENDICULAR TO TOP OF STOP SIGN		
	STOP 0090 1302 0482	1	750	750	0.56		1																									BACK TO BACK		E-143M
TOTALS					m² ~~4.64~~ 5.49	m²	EA. 5	m²			m 32.2	m	m	m ~~32.2~~ 121′	m	m 32.2	m	EA		kg	kg	kg	EA.	kg	kg	kg	kg	EA.	EA.	kg					

FUR 12-21-04 DAN TYLER

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: BRATTLEBORO
PROJECT NUMBER: ST-STP 2303(I)S

FILE NAME: /PAVE/OID026/PD026.dgn
PROJECT LEADER: WRH
DESIGNED BY: -
CLD REF. NO.: pd026tss3.1
PLOT DATE: $DATE$
DRAWN BY: JAC
CHECKED BY: NLL
SHEET 37 OF 55