STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 6

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	49 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	TUBULAR STEEL Ø (mm) FOUNDATION	kg/m 75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																									
STA 8+362 LT	MELROSE ST	1					1				1			X 13′		X																	SALVAGED SIGN TO BE INSTALLED USING TOP MOUNTING BRACKET, MOUNTED PERPENDICULAR TO TOP OF STREET SIGN		
	WESTERN AVE	1					1																										SALVAGED SIGN TO BE INSTALLED USING TOP MOUNTING BRACKET, MOUNTED 0.3M FROM AND PERPENDICULAR TO TOP OF STOP SIGN		
	STOP 0090 1302 0519	1 1	750	750	0.56		1																										BACK TO BACK		E-143M
STA 8+538 RT		1	750	750	0.56						1			X 14′		X																	FLUORESCENT YELLOW-GREEN SHEETING		E-152M
		1	600	300	0.18																											FLUORESCENT YELLOW-GREEN SHEETING	53	
STA 8+540 LT		1	750	750	0.56						1			X 14′		X																	FLUORESCENT YELLOW-GREEN SHEETING		E-152M
		1	600	300	0.18																											FLUORESCENT YELLOW-GREEN SHEETING	53	
STA 8+754 RT	BROOKSIDE DR	1					1				1			X 13′		X																	SALVAGED SIGN TO BE INSTALLED USING TOP MOUNTING BRACKET, MOUNTED PERPENDICULAR TO TOP OF STREET SIGN		
	WESTERN AVE	1					1																										SALVAGED SIGN TO BE INSTALLED USING TOP MOUNTING BRACKET, MOUNTED 0.3M FROM AND PERPENDICULAR TO TOP OF STOP SIGN		
	STOP 0090 1302 0544	1 1	750	750	0.56		1																										BACK TO BACK		E-143M
STA 8+761 RT		1	750	750	0.56						1			X 14′		X																	FLUORESCENT YELLOW-GREEN SHEETING		E-152M
		1	600	300	0.18																											FLUORESCENT YELLOW-GREEN SHEETING	53	
STA 8+762 LT		1	750	750	0.56						1			X 14′		X																	FLUORESCENT YELLOW-GREEN SHEETING		E-152M
		1	600	300	0.18																											FLUORESCENT YELLOW-GREEN SHEETING	53	
												m	m	m	m	m	m	EA	kg	kg	kg		kg	kg	kg	kg								
														27.6		27.6																				
TOTALS					m² 4.08	m²	EA. 6	m²				m 82′ = 24.99m 27.6			m 27.6				kg	EA.	kg		EA.	EA.	kg											

DAN TYLER

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: BRATTLEBORO
PROJECT NUMBER: ST-STP 2303(I)S

FILE NAME: /PAVE/OID026/PD026.dgn
PROJECT LEADER: WRH
DESIGNED BY: -
CLD REF. NO.: pd026tss6.I

PLOT DATE: $DATE$
DRAWN BY: JAC
CHECKED BY: NLL
SHEET 40 OF 55