STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 9

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	49 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	TUBULAR STEEL Ø (mm) FOUNDATION	kg/m 75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																								
STA 9+455 LT	BRATTLE ST	1					1				1			X 13′		X																	SALVAGED SIGN TO BE INSTALLED USING TOP MOUNTING BRACKET, MOUNTED PERPENDICULAR TO TOP OF STREET SIGN		
	WESTERN AVE	1					1																										SALVAGED SIGN TO BE INSTALLED USING TOP MOUNTING BRACKET, MOUNTED 0.3M FROM AND PERPENDICULAR TO TOP OF STOP SIGN		
	STOP	1	750	750	0.56																													E-143M
STA 9+473 LT	NO OUTLET	1	750	750	0.56						1			X 14′		X																		53	
STA 9+481 RT		1	750	750	0.56						1			X 14′		X																FLUORESCENT YELLOW-GREEN SHEETING		E-152M
		1	600	300	0.18																										FLUORESCENT YELLOW-GREEN SHEETING	53	
STA 9+483 LT		1	750	750	0.56						1			X 14′		X																FLUORESCENT YELLOW-GREEN SHEETING		E-152M
		1	600	300	0.18																										FLUORESCENT YELLOW-GREEN SHEETING	53	
STA 9+515 LT	LANE ENDS MERGE LEFT	1	750	750	0.56						1			X 14′		X																	53	
STA 9+520 RT	ONLY	1	1200	750	0.90						2			13′ X 13′		X																		E-145M
STA 9+531 LT	DO NOT ENTER / STOP	1 1	750 750	750 750	0.56 0.56						1			X 11′		X																BACK TO BACK		E-143M E-143M
	ONE WAY	1	900	300	0.27																													E-142M
STA 9+540 LT	DO NOT ENTER / STOP	1 1	750 750	750 750	0.56 0.56						1			X 13′		X																BACK TO BACK		E-143M E-143M
	ONE WAY / ONE WAY	1 1	900 900	300 300	0.27 0.27																											BACK TO BACK		E-142M E-142M
TOTALS					m² 7.11	m²	EA. 2	m²				m	m	m 41.4	m	m 41.4	m		EA	kg	kg	kg		kg	kg	kg	kg	EA.	EA.	EA.	kg				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

FUR 12-21-04

DAN TYLER 119′ = 36.27m

PROJECT NAME: BRATTLEBORO
PROJECT NUMBER: ST-STP 2303(I)S

FILE NAME: /PAVE/OID026/PD026.dgn
PROJECT LEADER: WRH
DESIGNED BY: -
CLD REF. NO.: pd026tss9.I

PLOT DATE: $DATE$
DRAWN BY: JAC
CHECKED BY: NLL
SHEET 43 OF 55