STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 15

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	49 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	TUBULAR STEEL Ø (mm) FOUNDATION	kg/m 75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																									
STA 10+565 LT	NO PARKING THIS SIDE OF STREET	1					1				1			X 13′		X																			
STA 10+600 RT	TRUCKS USE LOWER GEAR	1					1				1			X 14′		X																			E-152M
STA 10+631 RT	EAST	1	600	300	0.18						1			14′		X																	X		E-136BM
	TO	1	600	300	0.18						1			X 14′		X																			E-136BM
	VERMONT 9	1	600	600	0.36																														E-136BM
	VERMONT 30	1	600	600	0.36																														E-136BM
	↖	1	525	375	0.20																														E-136BM
	↖	1	525	375	0.20																														E-135M
STA 10+645 LT	CHESTNUT HILL	1					1				1			X 13′		X																		SALVAGED SIGN TO BE INSTALLED USING TOP MOUNTING BRACKET, MOUNTED PERPENDICULAR TO TOP OF STREET SIGN		
	WESTERN AVE	1					1																											SALVAGED SIGN TO BE INSTALLED USING TOP MOUNTING BRACKET, MOUNTED 0.3M FROM AND PERPENDICULAR TO TOP OF STOP SIGN		
	STOP	1	750	750	0.56																														E-143M
STA 10+657 RT	WEST	1	600	300	0.18						1			14′		X																			E-136BM
	TO	1	600	300	0.18						1			X 14′		X																			E-135M
	VERMONT 9	1	600	600	0.36																														E-136BM
	INTERSTATE 91	1	600	600	0.36																														E-135M
	↗	1	525	375	0.20																														E-136BM
	↗	1	525	375	0.20																														E-135M
STA 10+690 RT	GREEN ST	1					1				1			X 13′		X																			
	STOP	1	750	750	0.56																														E-143M
TOTALS		m² 4.08			m²		EA. 5		m²			m 27.6			m 27.6					kg			EA.		kg					EA.	EA.	kg				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

FUR 12-21-04

DAN TYLER

m m m m m m EA kg kg kg kg kg kg kg

27.6 27.6

109′ = 33.22m

PROJECT NAME: BRATTLEBORO
PROJECT NUMBER: ST-STP 2303(I)S

FILE NAME: /PAVE/OID026/PD026.dgn
PROJECT LEADER: WRH
DESIGNED BY: -
CLD REF. NO.: pd026tssl5.i

PLOT DATE: $DATE$
DRAWN BY: JAC
CHECKED BY: NLL
SHEET 49 OF 55