



U.S. ROUTE 7 LIST OF TH'S AND STREETS FOR CONSTRUCTION SIGNS			
TOWN HIGHWAY NUMBER	ROAD WORK AHEAD	END ROAD WORK	OTHER
BEGIN PROJECT	2	1	
RAMP A	2		
RAMP C		1	
RAMP B		1	
RAMP D	2		
MOUNTAIN VIEW RD.	2	1	
LOWER MOUNTAIN VIEW RD.	2	1	
HERCULES RD.	2	1	
RATHE RD.	2	1	
CHAMPLAIN DR.	2	1	
END PROJECT	2	1	
TOTAL	18	9	

CONSTRUCTION APPROACH SIGNING
SEE STD. E-100 FOR ADDITIONAL SIGN PLACEMENT

PAYMENT FOR CONSTRUCTION SIGNING WILL BE
MADE UNDER CONTRACT ITEM 64I.I0.

SIGN LEGEND

- RWA = ROAD WORK AHEAD
- RW500 = ROAD WORK 500 FEET
- ERW = END ROAD WORK
- SRWA = SIDE ROAD WORK AHEAD

NOTE:

THE RESIDENT ENGINEER AT HIS OR HER
DISCRETION SHALL ELIMINATE CONSTRUCTION
APPROACH SIGNS FOR DEAD END/NO OUTLET
TOWN HIGHWAYS OR TOWN HIGHWAYS THAT
CONNECT ON BOTH SIDES OF THE PROJECT.

PROJECT NAME: COLCHESTER	PLOT DATE: 23-APR-2009 15:3
PROJECT NUMBER: STP 2307(1)s	DRAWN BY: LSW
FILE NAME: /pave01d044/p01d044.dgn	CHECKED BY: LSW
PROJECT LEADER: MW	SHEET 26 OF 26
IPARM NAME: p01d044cas.i	