STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 18

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (in)	SIGN DIMENSIONS HEIGHT (in)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.0 lb/ft 2.16	SQUARE STEEL (in) 2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) 3.0 lb/ft 1.3	TUBULAR ALUMINUM Ø (in) 4.0 lb/ft 1.7	TUBULAR ALUMINUM Ø (in) 4.0 MOD lb/ft 1.7	TUBULAR STEEL Ø (in) FOUND-ATION	TUBULAR STEEL Ø (in) 3.0 lb/ft 7.6	TUBULAR STEEL Ø (in) 3.5 lb/ft 9.0	TUBULAR STEEL Ø (in) 4.0 lb/ft 10.8	TUBULAR STEEL Ø (in) 5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
												OPTION ITEMS																							
US BR4 145+10 C.L.		1	24	30	5.0						1			X		X		X	X														R4-7		E-144
		2	18	18	4.50																												OMI-1		E-150
US BR4 146+36 LT		1	18	18	2.25						1			X		X		X	X														OMI-1		E-150
US BR4 148+73 RT		2 2	48 48	9 9	6.00 6.00																												PEDESTAL MOUNTED R15-1 OVERHEAD MOUNTED R15-1		E-190 E-190
US BR4 149+28 LT		2 2	48 48	9 9	6.00 6.00																												PEDESTAL MOUNTED R15-1 OVERHEAD MOUNTED R15-1		E-190 E-190
CONNECTOR 6+16 LT		1	36	36	9.00						2			X		X		X															W3-3		E-152
SUBTOTALS SIGN SUMMARY SHEET 16					39.5									79.0			79.0																		
SUBTOTALS SIGN SUMMARY SHEET 17					29.75	126.0								66.0			66.0																		
SUBTOTALS SIGN SUMMARY SHEET 18					44.5									40.0			40.0																		
SUBTOTALS USRB4					113.75	126.0								185.0			185.0																		
ROUNDING					0.75	0.0								0.0			0.0																		
TOTALS USRB4					114.00	126.0								185.0			185.0																		
												FT	FT	FT	FT	FT	FT		EA 3	LB	LB	LB		LB	LB	LB	LB								
PROJECT TOTALS					SF 114.00	SF 126.0	EA.	SF				FT 185.0			FT 185.0					LB			EA.	LB				EA.	EA.	LB				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: WEST RUTLAND
PROJECT NUMBER: STP 2601(1)S

FILE NAME: /pave/01d046/pd046.dgn
PROJECT LEADER: WOOLAVER
DESIGNED BY: JLR
pd046tsl8.1

PLOT DATE: 06-FEB-2009 15:2
DRAWN BY: JLR
CHECKED BY: JLR
SHEET 44 OF 45