

QUANTITY SHEET 1



SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
						ROADWAY	ROADWAY (NO FED./ STATE PARTI.)	BRIDGE	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
						370	85			455		CM	COMMON EXCAVATION	203.15	5.7			
						2				2		CM	SOLID ROCK EXCAVATION	203.16	0.6			
						0.5				0.5		CM	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	-			
						34620				34620		SM	COLD PLANING, BITUMINOUS PAVEMENT	210.10	342			
						565	105			670		T	SUBBASE OF CRUSHED GRAVEL, FINE GRADED	301.28	12			
						115				115		T	AGGREGATE SHOULDERS, RAP	402.13	2			
						7545				7545		KG	EMULSIFIED ASPHALT	404.65	76			
						0.5				0.5		LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50	-			
						5100				5100		T	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT (PG 64-28)	490.30	56			
						0.5				0.5		LU	AIR VOIDS PAY ADJUSTMENT (N.A.B.I.)	490.31				
								17		17		M	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG	516.10	1			
						1.5				1.5		CM	CONCRETE, CLASS B	541.25	0.3			
								3		3		CM	RAPID SETTING CONCRETE REPAIR MATERIAL WITH COARSE AGGREGATE	580.20	-			
						72				72		EACH	CHANGING ELEVATION OF DROP INLETS, CATCH BASINS, OR MANHOLES	604.40	-			
						1				1		EACH	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS I	604.412	-			
						24				24		EACH	CHANGING ELEVATION OF SEWER MANHOLES	604.42	-			
						20				20		HR	POWER GRADER RENTAL	608.15	2			
						10				10		HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	-			
						50				50		HR	POWER BROOM RENTAL, TYPE II	608.31	3			
							10			10		HR	TRUCK RENTAL	608.37	-			
							10			10		HR	LOADER RENTAL, TYPE I	608.40	-			
						5200				5200		CM	DUST CONTROL WITH WATER	609.10	57			
						460	230			690		M	CAST-IN-PLACE CONCRETE CURB, TYPE B	616.28	11.6			
						3				3		M	REMOVING AND RESETTING CURB	616.40	-			
						580	30			610		SM	PORTLAND CEMENT CONCRETE SIDEWALK, 125 MM	618.10	7.9			
						135				135		SM	DETECTABLE WARNING SURFACE	618.30	1.4			
						44				44		EACH	ADJUST ELEVATION OF VALVE BOX	629.20	-			
						470				470		HR	UNIFORMED TRAFFIC OFFICERS	630.10	6			
						495	5			500		HR	FLAGGERS	630.15	6			
									0.5	0.5		LS	FIELD OFFICE, ENGINEERS	631.10	-			
									0.5	0.5		LS	TESTING EQUIPMENT, CONCRETE	631.16	-			
									0.5	0.5		LS	TESTING EQUIPMENT, BITUMINOUS	631.17	-			
									0.5	0.5		LU	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.25	-			
						0.5				0.5		LS	MOBILIZATION/DEMobilIZATION	635.11	-			
						0.5				0.5		LS	TRAFFIC CONTROL	641.10	-			
						0.5				0.5		LS	PUBLIC RELATIONS OFFICER	641.12	-			
						2				2		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15				
						70				70		M	DURABLE 100 MM WHITE LINE, TYPE I TAPE	646.401	6			
						4720				4720		M	DURABLE 100 MM WHITE LINE, THERMOPLASTIC	646.402	50			
						10				10		M	DURABLE 100 MM YELLOW LINE, TYPE I TAPE	646.411	5			

PROJECT NAME: MIDDLEBURY
PROJECT NUMBER: STP 2304(1)S

FILE NAME: PD048
PROJECT MANAGER: WOOLAVER
DESIGNED BY: JLR
QUANTITY SHEET #1

PLOT DATE: 03/20/2007
DRAWN BY: JLR
CHECKED BY: JLR
SHEET 14 OF 103