


LOCATION			CURBED SIDEWALKS					DROP INLETS													MISC.		REMARKS							
STATION	STATION	POS.	203.15 COMM. EXCAV.	203.16 SOLID ROCK EXCAV.	301.28 SUBBASE OF CR. GRAV. (FINE)	616.28 CAST IN-PLACE CONC. CURB TYPE B	616.40 REMOVING AND RESETTING CURB	618.10 PORT. CEM. CONC. SDWK. 125 mm	604.40 CHANGE ELEV. D.I.	604.412 REHAB. D.I. CLASS I																		604.42 CHANGE ELEV. OF SMH EA	629.20 ADJUST ELEV. OF VALVE BOX EA	
MIDDLEBURY VT 30 ROADWAY (NO FED./STATE PARTICIPATION)			m3	m3	+	m	m	m2	EA	EA																				
2+515	2+518	LT	4.3		8.6	11.2		5.2																					CONSTRUCT BULB-OUT	
2+760	2+773	RT	11.7		17.9	11.9		23.8																					REMOVE EXISTING SIDEWALK, CONSTRUCT NEW SIDEWALK	
2+837	2+858	LT	8.0		13.9	24.1																								
2+850	2+871	RT	11.6		19.9	34.6																								
2+869	2+898	LT	10.2		17.5	30.5																								
2+874	2+894	RT	13.4		23.1	40.2																								
MIDDLEBURY VT 125 ROADWAY (NO FED./STATE PARTICIPATION)																														
0+589	0+611	RT	7.3			23.0																								
0+616	0+641	LT	8.3			26.0																								MATCH TO EXISTING @ 0+641
0+617	0+641	RT	8.0			25.0																								MATCH TO EXISTING @ 0+641
ROADWAY (NO FED./STATE PARTICIPATION)																														
SHEET 3 SUBTOTAL			82.8		100.9	226.5		29.0																						
ROUNDING			2.2		4.1	3.5		1.0																						
TOTAL			85.0		105.0	230.0		30.0																						
PROJECT SUBTOTAL			449.3	1.4	658.0	678.4	3.0	602.1	72	1																24	44			
PROJECT ROUNDING			5.7	0.6	12.0	11.6	0	7.9	0	0																0	0			
PROJECT TOTAL			455.0	2.0	670.0	690.0	3.0	610.0	72	1																24	44			

<b>ITEM DETAIL SHEET 3</b>	PROJECT :	MIDDLEBURY	PROJECT NO. :	STP 2304(I)S
	DESIGN FILE NAME:	/pave/01d048/pd048.dgn	PLOT DATE:	06-OCT-2008
	IPARM FILE NAME:	pd0481d03.1	SURVEY DATE:	10/03
	PROJECT LEADER:	PTS	DRAWN BY:	MRS
		pd048.dgn	SHEET:	18 OF 103