STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 1

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (mm)	SIGN DIMENSIONS HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	FLANGED CHANNEL kg/m 3.0	FLANGED CHANNEL kg/m 4.5	SQUARE STEEL (mm) 44 kg/m 3.4	SQUARE STEEL (mm) 50 kg/m 3.9	SQUARE STEEL (mm) 63 kg/m 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) 75 kg/m 1.9	TUBULAR ALUMINUM Ø (mm) 100 kg/m 2.5	TUBULAR ALUMINUM Ø (mm) 100 MOD kg/m 2.5	TUBULAR STEEL Ø (mm) FOUNDATION	TUBULAR STEEL Ø (mm) 75 kg/m 11.3	TUBULAR STEEL Ø (mm) 89 kg/m 13.4	TUBULAR STEEL Ø (mm) 100 kg/m 16.1	TUBULAR STEEL Ø (mm) 125 kg/m 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	W-SHAPE STEEL FTG. SIZE 750 mm	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
											OPTION ITEMS																									
MIDDLEBURY VT RTE 30																																			
STA 1+077 RT		2	600	750	0.90						2					X		X															PLACE SIGNS AT EACH END OF ISLAND.		E-144
		4	600	600	1.44																											BACK TO BACK		E-150
STA 1+086 RT		1	750	750	0.56						1					X		X																E-143
STA 1+520 RT		1	750	750	0.56						1					X		X															FLUORESCENT YELLOW-GREEN SHEETING		E-152
		1	600	300	0.18																											W16-9P FLUORESCENT YELLOW-GREEN SHEETING		
STA 1+648 LT		1	750	750	0.56						1					X		X															FLUORESCENT YELLOW-GREEN SHEETING		E-152
		1	600	300	0.18																											FLUORESCENT YELLOW-GREEN SHEETING		E-152
STA 1+648 RT		1	750	750	0.56						1					X		X															FLUORESCENT YELLOW-GREEN SHEETING		E-152
		1	600	300	0.18																											FLUORESCENT YELLOW-GREEN SHEETING		E-152
STA 1+825 RT		1	750	750	0.56						1					X		X															FLUORESCENT YELLOW-GREEN SHEETING		E-152
		1	600	300	0.18																											FLUORESCENT YELLOW-GREEN SHEETING		E-152
STA 1+826 LT		1	750	750	0.56						1					X		X															FLUORESCENT YELLOW-GREEN SHEETING		E-152
		1	600	300	0.18																											FLUORESCENT YELLOW-GREEN SHEETING		E-152
											m	m	m	m	m	m		EA	kg	kg	kg		kg	kg	kg	kg								
															36.8																				
FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE ROADWAY TRAFFIC AND SAFETY SECTION'S "SIGN POST DESIGN GUIDELINE."	**TOTALS**		m^2 6.60	m^2	EA.	m^2		m		m 36.8		kg	EA.	kg		EA.	EA.	kg																

PROJECT : MIDDLEBURY	PROJECT NO. : STP 2304(I)S
DESIGN FILE NAME: /pave/01d048/pb048.dgn	
IPARM FILE NAME: pb048ts01.i	PLOT DATE: 06-OCT-2008
SURVEYED BY: CLD ENGINEERS INC	SURVEY DATE: 10-03
SQUAD LEADER: PTS	DRAWN BY: MRS
	SHEET: 42 OF 103