STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 2

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	50 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	TUBULAR STEEL Ø (mm) FOUNDATION	kg/m 75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
											OPTION ITEMS																									
STA 1+910 RT		1	750	750	0.56						1					X		X															FLUORESCENT YELLOW-GREEN SHEETING		E-152
		1	600	300	0.18																											FLUORESCENT YELLOW-GREEN SHEETING		E-152
STA 1+914 LT		1	750	750	0.56						1					X		X															FLUORESCENT YELLOW-GREEN SHEETING		E-152
		1	600	300	0.18																											FLUORESCENT YELLOW-GREEN SHEETING		E-152
STA 1+960 RT		1	600	750	0.45						1					X		X																	E-142
STA 2+027 RT		1	750	750	0.56						1					X		X															FLUORESCENT YELLOW-GREEN SHEETING		E-152
		1	600	300	0.18																											FLUORESCENT YELLOW-GREEN SHEETING		E-152
STA 2+031 LT		1	750	750	0.56						1					X		X															FLUORESCENT YELLOW-GREEN SHEETING		E-152
		1	600	300	0.18																											FLUORESCENT YELLOW-GREEN SHEETING		E-152
STA 2+034 LT	S Main St	1	750	225	0.17				1																							SIGN TO BE INSTALLED USING TOP MOUNTING BRACKET, MOUNTED PERPENDICULAR TO TOP OF STREET SIGN		E-123
	Storrs Ave	1	900	225	0.20																											SIGN TO BE INSTALLED USING TOP MOUNTING BRACKET, MOUNTED 0.3M FROM AND PERPENDICULAR TO TOP OF STOP SIGN		E-123
																																RETAIN SIGN		
STA 2+220 RT		1	750	750	0.56						1					X		X															FLUORESCENT YELLOW-GREEN SHEETING		E-152
		1	600	450	0.27																											FLUORESCENT YELLOW-GREEN SHEETING		E-152
											m	m	m	m	27.6	m		EA	kg	kg	kg		kg	kg	kg	kg								
TOTALS		m² 4.61	m²	EA.	m²						m			m 27.6				kg	EA.	kg						EA.	EA.	kg					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE ROADWAY TRAFFIC AND SAFETY SECTION'S "SIGN POST DESIGN GUIDELINE."

PROJECT : MIDDLEBURY	PROJECT NO. : STP 2304(I)S
DESIGN FILE NAME: /pave/01d048/pb048.dgn	
IPARM FILE NAME: pb048ts02.i	PLOT DATE: 06-OCT-2008
SURVEYED BY: CLD ENGINEERS INC	SURVEY DATE: 10-03
SQUAD LEADER: PTS	DRAWN BY: MRS
pd048.dgn	SHEET: 43 OF 103