STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 6

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	50 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	TUBULAR STEEL Ø (mm) FOUNDATION	kg/m 75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																									
STA 2+517 LT	↑ CORNWALL 4	1	1825	300	0.55						2						X	X																		E-123
	WEYBRIDGE 3 ↗	1	1825	300	0.55																															E-123
	BRIDPORT 8 ↗	1	1825	300	0.55																															E-123
	SOUTH / WEST / NORTH	1	600	300	0.18																												X	SIGN FRAMES E-123		E-136B
		1	600	300	0.18																															E-136B
		1	600	300	0.18																															E-136B
	VERMONT 30 / VERMONT 125 / 23	1	600	600	0.36																															E-136B
		1	750	600	0.45																															E-136B
		1	600	600	0.36																															E-136C
	↑ ↗ ↗	1	525	375	0.20																															E-136B
		1	525	375	0.20																															E-136B
		1	525	375	0.20																															E-136C
STA 2+536 LT	Park St						1				1					X		X																SALVAGED SIGN TO BE INSTALLED USING TOP MOUNTING BRACKET, MOUNTED PERPENDICULAR TO TOP OF STREET SIGN		
	DO NOT ENTER	1	750	750	0.56																															E-143
STA 2+524 LT	STOP	1	750	750	0.56						1					X		X																			E-143
STA 2+527 LT	RESERVED PARKING ♿	1	300	450	0.14						1					X		X																R7-8M	54	
STA 2+577 RT	NO PARKING BEYOND THIS SIGN						1				1					X			X																	
STA 2+718 RT	RESERVED PARKING ♿	1	300	450	0.14						1					X			X															R7-8M	54	
												m	m	m	m	m 23.0	m 9.20		EA 2	kg	kg	kg		kg	kg	kg	kg							
TOTALS		m² 5.36		m²	EA. 2		m²					m			m 32.2					kg			EA.	kg				EA.	EA.	kg				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE ROADWAY TRAFFIC AND SAFETY SECTION'S "SIGN POST DESIGN GUIDELINE."

PROJECT : MIDDLEBURY	PROJECT NO. : STP 2304(I)S
DESIGN FILE NAME: /pave/0ld048/pb048.dgn	
IPARM FILE NAME: pb048ts06.I	PLOT DATE: 06-OCT-2008 I
SURVEYED BY: CLD ENGINEERS INC	SURVEY DATE: I0-03
SQUAD LEADER: PTS	DRAWN BY: MRS
	SHEET: 47 OF I03