STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 12

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	50 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	TUBULAR STEEL Ø (mm) FOUNDATION	kg/m 75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																									
STA 1+509 LT	WEYBRIDGE 3 →	1	1825	300	0.55						2						X	X														X	SIGN FRAMES E-123		E-123
	↑ BRIDPORT 8	1	1825	300	0.55																														E-123
	↑ BRIDGE TO NY 15	1	1825	300	0.55																														E-123
	WEST / NORTH	1 1	600 600	300 300	0.18 0.18																														E-136B E-136C
	VERMONT 125 / 23	1 1	750 600	600 600	0.45 0.36																														E-136B E-136C
	↑ / →	1 1	525 525	375 375	0.20 0.20																														E-136B E-136C
STA 1+555 RT	CORNWALL 4 →	1	1825	300	0.55						2					X		X																		E-123
	CASTLETON CORNERS 29 →	1	1825	300	0.55																														E-123
STA 1+592 LT		1	750	750	0.56						1					X		X																FLUORESCENT YELLOW-GREEN SHEETING		E-152
	NEXT 1/2 MILE	1	600	300	0.18																													FLUORESCENT YELLOW-GREEN SHEETING		E-152
STA 1+603 CL		1	600	750	0.90						1					X		X																		E-144
		2	600	600	0.72																													BACK TO BACK		E-150
STA 1+604 RT	YIELD 900 X 900 X 900 / DO NOT ENTER	1 1	 750	 750	0.35 0.56						1					X		X																BACK TO BACK		E-146 E-143
STA 1+618 RT	YIELD 900 X 900 X 900	1			0.35						1					X		X																		E-146
												m	m	m	m	m 27.6	m 9.20		EA	kg	kg	kg		kg	kg	kg	kg							
TOTALS			m² 7.94	m²	EA.	m²						m			m 36.8					kg			EA.	kg				EA.	EA.	kg				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE ROADWAY TRAFFIC AND SAFETY SECTION'S "SIGN POST DESIGN GUIDELINE."

PROJECT : MIDDLEBURY	PROJECT NO. : STP 2304(I)S
DESIGN FILE NAME: /pave/0ld048/pb048.dgn	
IPARM FILE NAME: pb048tsl2.1	PLOT DATE: 06-OCT-2008
SURVEYED BY: CLD ENGINEERS INC	SURVEY DATE: 10/03
SQUAD LEADER: PTS	DRAWN BY: MRS
	SHEET: 53 OF 103