STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 2

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	50 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	TUBULAR STEEL Ø (mm) FOUNDATION	kg/m 75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																									
STA 7+138 LT	COURT ST						1				1					X		X																SIGN TO BE INSTALLED USING TOP MOUNTING BRACKET, MOUNTED PERPENDICULAR TO TOP OF STREET SIGN		
	CHARLES AVE						1																													
STA 7+168 LT	STOP HERE ON RED	1	600	900	0.54						1					X		X																R10-6		E-140
STA 7+200 RT	THOMAS ST						1				1					X		X																		
	STOP	1	750	750	0.56																													R1-1		E-143
STA 7+225 LT	MIDDLEBURY UNION HIGH SCHOOL	1	1825	500	0.91						2					X		X																D1-2(R)		E-123
STA 7+320 LT		1	900	900	0.81						2					X		X																S1-1 FLUORESCENT YELLOW - GREEN SHEETING		E-153
	AHEAD	1	900	600	0.54																													W16-9P FLUORESCENT YELLOW - GREEN SHEETING		
STA 7+369 RT	SPEED LIMIT 25	1	600	750	0.45						1					X		X																R2-1		E-142
STA 7+434 RT	MARY HOGAN ELEMENTARY SCHOOL	1	1825	500	0.91						2					X		X																D1-2(R)		E-123
STA 7+476 RT	NO TURN ON RED	1	600	750	0.45						1					X		X																R10-11A		E-140
STA 7+496 RT	STOP HERE ON RED	1	600	900	0.54						1					X		X																R10-6		E-140
STA 7+532 LT	ONLY	1	750	750	0.56						1					X		X																VR-921		E-145A
												m	m	m	m	m 59.8	m		EA	kg	kg	kg		kg	kg	kg	kg								
TOTALS		m² 6.27		m²	EA. 3	m²						m			m 59.8					kg			EA.	kg				EA.	EA.	kg					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE ROADWAY TRAFFIC AND SAFETY SECTION'S "SIGN POST DESIGN GUIDELINE."

PROJECT :	PROJECT NO. :
MIDDLEBURY	NH 2603(I)S

DESIGN FILE NAME: /pave/06b032/p06b032.dgn
IPARM FILE NAME: p06b032tss02.i
SURVEYED BY: CLD ENGINEERS INC
SQUAD LEADER: PTS
PLOT DATE: 06-OCT-2008
SURVEY DATE: 05-06
DRAWN BY: MRS
SHEET: 86 OF 103