STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 3

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	50 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	TUBULAR STEEL Ø (mm) FOUNDATION	kg/m 75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																								
STA 7+564 RT	BEGIN	1	600	300	0.18						1					X		X															M4-11		E-140
	CENTER LANE ONLY	1	600	900	0.54																											R3-9B		E-140
STA 7+569 LT	END	1	600	300	0.18						1					X		X															M4-6		E-140
	CENTER LANE ONLY	1	600	900	0.54																											R3-9B		E-140
STA 7+617 RT	END	1	600	300	0.18						1					X		X															M4-6		E-140
	CENTER LANE ONLY	1	600	900	0.54																											R3-9B		E-140
	ONLY	1	750	750	0.56																											VR-921		E-145A
STA 7+631 LT	BEGIN	1	600	300	0.18						1					X		X															M4-11		E-140
	CENTER LANE ONLY	1	600	900	0.54																											R3-9B		E-140
STA 7+672 LT	CROSS ST						1				1					X		X																		
	COURT ST						1																												
	NEIGHBORHOOD WATCH						1																												
STA 7+676 LT	STOP	1	750	750	0.56						1					X		X															R1-1		E-143
												m	m	m	m	27.6 m	m	EA	kg	kg	kg		kg	kg	kg	kg								
	TOTALS				m² 4.00	m²	EA. 3	m²				m			m 27.6					kg			EA.	kg				EA.	EA.	kg					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE ROADWAY TRAFFIC AND SAFETY SECTION'S "SIGN POST DESIGN GUIDELINE."

PROJECT :	PROJECT NO. :
MIDDLEBURY	NH 2603(I)S

DESIGN FILE NAME: /pave/06b032/p06b032.dgn
IPARM FILE NAME: p06b032tss03.i
SURVEYED BY: CLD ENGINEERS INC
SQUAD LEADER: PTS
PLOT DATE: 06-OCT-2008
SURVEY DATE: 05-06
DRAWN BY: MRS
SHEET: 87 OF 103