STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 4

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	50 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	TUBULAR STEEL Ø (mm) FOUND-ATION	kg/m 75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
STA 7+717 LT							1				1					X		X																	
							1																												
STA 7+765 RT		1	750	750	0.56						1					X		X															R1-1		E-143
STA 7+767 RT	MARY HOGAN DR						1				1					X		X																	
	COURT ST						1																												
	NEIGHBORHOOD WATCH						1																												
STA 7+786 RT		1	600	750	0.45						1					X		X															R2-1		E-142
STA 7+836 LT		1	600	750	0.45						1					X		X															R2-1		E-142
STA 7+870 LT	E. MIDDLEBURY 5	1	1825	300	0.55						2					X		X															D1-1		E-123
	BRANDON 8	1	1825	300	0.55																												D1-1		E-123
	MARY HOGAN ELEMENTARY SCHOOL ←	1	1825	500	0.91																												D1-2(R)		E-123
STA 7+890 RT		1	750	750	0.56						1					X		X															R3-7R		E-140
STA 7+894 LT	TRAVEL INFORMATION / TRAVEL INFORMATION						2				1					X		X															BACK TO BACK		
												m	m	m	m	m 41.4	m		EA	kg	kg	kg		kg	kg	kg	kg							
TOTALS		m² 4.03			m²		EA. 7		m²			m			m	41.4				kg			EA.	kg				EA.	EA.	kg				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE ROADWAY TRAFFIC AND SAFETY SECTION'S "SIGN POST DESIGN GUIDELINE."

PROJECT :	PROJECT NO. :
MIDDLEBURY	NH 2603(I)S

DESIGN FILE NAME: /pave/06b032/p06b032.dgn
IPARM FILE NAME: p06b032tss04.i
SURVEYED BY: CLD ENGINEERS INC
SQUAD LEADER: PTS
PLOT DATE: 06-OCT-2008
SURVEY DATE: 05-06
DRAWN BY: MRS
SHEET: 88 OF 103