STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 12

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	50 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	TUBULAR STEEL Ø (mm) FOUNDATION	kg/m 75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																									
STA 8+168 LT	SOUTH / SOUTH	1	600	300	0.18						2												2	113.0							X	M3-3 M3-3 (SIGN FRAMES E-123)		E-136A E-136B
	7 / VERMONT 30	1	600	600	0.36																											M1-4		E-136A E-136B
	↑ / →	1	525	375	0.20																											M6-3 M6-1		E-136A E-136B
	TO / TO	1	600	300	0.18																											M4-5 M4-5		E-136B E-136B
	EAST / WEST	1	600	300	0.18																											M3-2 M3-4		E-136B E-136B
	VERMONT 125 / VERMONT 125	1	750	600	0.45																													E-136B E-136B
	↑ / →	1	525	375	0.20																											M6-3 M6-1		E-136B E-136B
STA 8+176 RT		1	750	750	0.56						1					X		X														W11-2 FLUORESCENT YELLOW - GREEN SHEETING		E-152
		1	600	300	0.18																											W16-7P FLUORESCENT YELLOW - GREEN SHEETING		E-152
STA 8+185 LT	NORTH PLEASANT ST						1				1					X		X																	
STA 8+185 LT		1	750	750	0.56						1					X		X														W11-2 FLUORESCENT YELLOW - GREEN SHEETING		E-152
		1	600	300	0.18																											W16-7P FLUORESCENT YELLOW - GREEN SHEETING		E-152
STA 8+185 LT		1	600	600	0.36																											R3-2 BACK TO BACK WITH RETAINED SIGNS		E-143
STA 8+190 LT	RESERVED PARKING	1	300	450	0.14						1					X		X														R7-8M	101	
												m	m	m	m	18.4 m	m		EA	kg	kg	kg		kg 113.0	kg	kg	kg							
TOTALS			m² 5.48	m²	EA. 1	m²						m			m 18.4					kg			EA. 2	kg 113.0				EA.	EA.	kg				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE ROADWAY TRAFFIC AND SAFETY SECTION'S "SIGN POST DESIGN GUIDELINE."

PROJECT :	PROJECT NO. :
MIDDLEBURY	NH 2603(I)S

DESIGN FILE NAME: /pave/06b032/p06b032.dgn
IPARM FILE NAME: p06b032tssl2.I
SURVEYED BY: CLD ENGINEERS INC
SQUAD LEADER: PTS
PLOT DATE: 06-OCT-2008
SURVEY DATE: 05-06
DRAWN BY: MRS
SHEET: 96 OF 103