STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 13

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	50 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	TUBULAR STEEL Ø (mm) FOUNDATION	kg/m 75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																									
STA 8+221 RT	NORTH	1	600	300	0.18						1					X		X																M3-1		E-136A
	7	1	600	600	0.36																												M1-4		E-136A
STA 8+239 LT	E. MIDDLEBURY 5	1	1825	300	0.55						2						X	X															D1-1		E-123
	BRANDON 18	1	1825	300	0.55																												D1-1		E-123
	CORNWALL 4	1	1825	300	0.55																												D1-1		E-123
	BRIDPORT 8	1	1825	300	0.55																												D1-1		E-123
	H	1	600	600	0.36																												D9-2		E-132
	⟶	1	600	150	0.09																														E-132
STA 8+271 RT	JOHN GRAHAM CT						1				1					X		X																	E-123
STA 8+276 RT	R	1	300	300	0.09						1					X		X															R8-3A		E-143
STA 8+290 RT	VERGENNES 13	1	1825	300	0.55						2					X		X															D1-1		E-123
	BURLINGTON 32	1	1825	300	0.55																												D1-1		E-123
TOTALS		m² 4.38	m²	EA. 1	m²							m	m	m	m	m 23.0	m 9.2		EA	kg	kg	kg	EA.	kg	kg	kg	kg	EA.	EA.	kg					
															m 32.2																				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE ROADWAY TRAFFIC AND SAFETY SECTION'S "SIGN POST DESIGN GUIDELINE."

PROJECT :	PROJECT NO. :
MIDDLEBURY	NH 2603(I)S

DESIGN FILE NAME: /pave/06b032/p06b032.dgn
IPARM FILE NAME: p06b032tssl3.I
SURVEYED BY: CLD ENGINEERS INC
SQUAD LEADER: PTS
PLOT DATE: 06-OCT-2008
SURVEY DATE: 05-06
DRAWN BY: MRS
SHEET: 97 OF 103