STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 14

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	50 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	TUBULAR STEEL Ø (mm) FOUNDATION	kg/m 75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																									
STA 8+322 LT	JCT	1	525	375	0.20						1						X	X																M2-1		E-136B
	VERMONT 30	1	600	600	0.36																															E-136B
	TO	1	600	300	0.18																												M4-5		E-136B
	WEST	1	600	300	0.18																												M3-4		E-136B
	VERMONT 125	1	750	600	0.45																															E-136B
STA 8+326 LT	ONE WAY ONE WAY	1 1	900 900	300 300	0.27 0.27						1					X		X															R6-1R R6-1L BACK TO BACK		E-142 E-142
STA 8+329 RT	NORTH PLEASANT ST						1				1					X		X															SIGN TO BE INSTALLED USING TOP MOUNTING BRACKET, MOUNTED PERPENDICULAR TO TOP OF STREET SIGN		
	SEMINARY ST						1																										SIGN TO BE INSTALLED USING TOP MOUNTING BRACKET, MOUNTED 0.3M FROM AND PERPENDICULAR TO TOP OF STOP SIGN		
	STOP	1	750	750	0.56																												R1-1		E-143
STA 8+350 RT	EMERGENCY VEHICLES	1	900	900	0.81						2					X		X															VW-544		E-154
STA 8+368 LT		1	750	750	0.56						1					X		X															W11-2 FLUORESCENT YELLOW - GREEN SHEETING		E-152
	AHEAD	1	900	600	0.54																												W16-9P FLUORESCENT YELLOW - GREEN SHEETING		
STA 8+380 RT	SPEED LIMIT 25	1	600	750	0.45						1					X		X															R2-1		E-142
		1	300	300	0.09																												R8-3A		E-143
												m	m	m	m	m 27.6	m 4.6		EA	kg	kg	kg		kg	kg	kg	kg								
TOTALS		m² 4.92	m²	EA. 2	m²							m			m 32.2					kg			EA.	kg				EA.	EA.	kg					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE ROADWAY TRAFFIC AND SAFETY SECTION'S "SIGN POST DESIGN GUIDELINE."

PROJECT :	PROJECT NO. :
MIDDLEBURY	NH 2603(I)S

DESIGN FILE NAME: /pave/06b032/p06b032.dgn
IPARM FILE NAME: p06b032tssl4.I
SURVEYED BY: CLD ENGINEERS INC
SQUAD LEADER: PTS
PLOT DATE: 06-OCT-2008
SURVEY DATE: 05-06
DRAWN BY: MRS
SHEET: 98 OF 103