STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 16

VAOT Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	50 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	TUBULAR STEEL Ø (mm) FOUNDATION	kg/m 75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																									
STA 9+046 RT	DO NOT ENTER	1	750	750	0.56						1					X		X																R5-1		E-143
	ONE WAY	1	900	300	0.27																													R6-1L		E-142
STA 9+052 RT	STOP / DO NOT ENTER	1 1	750 750	750 750	0.56 0.56						1					X		X																R1-1 R5-1 BACK TO BACK		E-143 E-143
	0070 0111 0564	1 1	600 150	600 250	0.36 0.04																													R3-2 BACK TO BACK		E-143 E-138
	ONE WAY	1	900	300	0.27																													R6-1L		E-142
	SUBTOTALS SHEET 1				4.90		3									41.4	0.00																			
	SUBTOTALS SHEET 2				6.27		3									59.8	0.00																			
	SUBTOTALS SHEET 3				4.00		3									27.6	0.00																			
	SUBTOTALS SHEET 4				4.03		7									41.4	0.00																			
	SUBTOTALS SHEET 5				4.40		2									9.20	9.20																			
	SUBTOTALS SHEET 6				6.36		1									23.0	9.20																			
	SUBTOTALS SHEET 7				5.11		0									36.8	0.00																			
	SUBTOTALS SHEET 8				6.79		0									18.4	9.20																			
	SUBTOTALS SHEET 9				5.80		0									23.0	4.60																			
	SUBTOTALS SHEET 10				6.02		1									36.8	0.00																			
	SUBTOTALS SHEET 11				3.52		0									27.6	0.00																			
	SUBTOTALS SHEET 12				5.48		1									18.4	0.00									2	113.0									
	SUBTOTALS SHEET 13				4.38		1									23.0	9.20																			
	SUBTOTALS SHEET 14				4.92		2									27.6	4.60																			
	SUBTOTALS SHEET 15				4.35		6									55.2	0.00																			
	SUBTOTALS SHEET 16				2.62		0									9.20	0.00																			
											m	m	m	m	478.4	m 46.0		EA	kg	kg	kg		kg 113.0	kg	kg	kg								
	PROJECT TOTALS				m² 78.95	m²	EA. 30	m²			m			m	524.4				kg			EA. 2	kg 113.0				EA.	EA.	kg					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE ROADWAY TRAFFIC AND SAFETY SECTION'S "SIGN POST DESIGN GUIDELINE."

PROJECT :	PROJECT NO. :
MIDDLEBURY	NH 2603(I)S
DESIGN FILE NAME: /pave/06b032/p06b032.dgn	
IPARM FILE NAME: p06b032tssl6.i	PLOT DATE: 06-OCT-2008
SURVEYED BY: CLD ENGINEERS INC	SURVEY DATE: 05-06
SQUAD LEADER: PTS	DRAWN BY: MRS
	SHEET: 100 OF 103