

QUANTITY SHEET 2



SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
ROADWAY	TRAINING	LANDSCAPING	EROSION CONTROL	WATER	WATER - (NO FEDERAL/STATE)	FULL C.E. ITEMS	ROADWAY (TRAFFIC CONTROL)	SEWER	SEWER - (NO FEDERAL/STATE)	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
													BEGN OPTION CC					
24.3										24.3		M	375 CSP 1.63 (68 X 12)	601.0010	-			
24.3										24.3		M	375 RCP CLASS IV	601.0811	-			
24.3										24.3		M	375 CPER(SL)	601.2610	-			
													END OPTION CC					
													BEGN OPTION DD					
14.5										14.5		M	300 CAAP 1.52 (68 X 12)	601.0205	-			
14.5										14.5		M	300 PCCSP 1.63 (68 X 12)	601.0405	-			
14.5										14.5		M	300 RCP CLASS III	601.0805	-			
14.5										14.5		M	300 CPER(SL)	601.2605	-			
													END OPTION DD					
													BEGN OPTION EE					
86							39.1			125.1		M	375 CAAP 1.52 (68 X 12)	601.0210	-			
86							39.1			125.1		M	375 PCCSP 1.63 (68 X 12)	601.0410	-			
86							39.1			125.1		M	375 RCP CLASS III	601.0810	-			
86							39.1			125.1		M	375 CPER(SL)	601.2610	-			
													END OPTION EE					
													BEGN OPTION FF					
574.8							29.5			604.3		M	450 CAAP 1.52 (68 X 12)	601.0215	-			
574.8							29.5			604.3		M	450 PCCSP 1.63 (68 X 12)	601.0415	-			
574.8							29.5			604.3		M	450 RCP CLASS III	601.0815	-			
574.8							29.5			604.3		M	450 CPER(SL)	601.2615	-			
													END OPTION FF					
													BEGN OPTION GG					
13.8										13.8		M	450 CAAP 1.52 (68 X 12)	601.0215	-			
13.8										13.8		M	450 PCCSP 1.63 (68 X 12)	601.0415	-			
													END OPTION GG					
													BEGN OPTION HH					
95.1							43.3			138.4		M	600 CAAP 1.52 (68 X 12)	601.0225	-			
95.1							43.3			138.4		M	600 PCCSP 1.63 (68 X 12)	601.0425	-			
95.1							43.3			138.4		M	600 RCP CLASS III	601.0825	-			
95.1							43.3			138.4		M	600 CPER(SL)	601.2620	-			
													END OPTION HH					
													BEGN OPTION II					
13.5							5			18.5		M	600 CAAP 1.52 (68 X 12)	601.0225	-			
13.5							5			18.5		M	600 PCCSP 1.63 (68 X 12)	601.0425	-			
													END OPTION II					

PROJECT NAME:	BRANDON
PROJECT NUMBER:	NH 019-3(495)
FILE NAME:	2b008_5qss1.xls
PROJECT LEADER:	CRB
DESIGNED BY:	PTS
QUANTITY SHEET #2	
PLOT DATE:	09/03/2009
DRAWN BY:	NLL
CHECKED BY:	PTS
SHEET	6 OF 546