

QUANTITY SHEET 7



SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
ROADWAY	TRAINING	LANDSCAPING	EROSION CONTROL	WATER	WATER - (NO FEDERAL/STATE)	FULL C.E. ITEMS	ROADWAY (TRAFFIC CONTROL)	SEWER	SEWER - (NO FEDERAL/STATE)	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
													END OPTION AB					
1										1		EACH	ANCHOR FOR STEEL BEAM RAIL	621.60	-			
711										711		M	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80	-			
							750			750		M	TEMPORARY TRAFFIC BARRIER	621.90	-			
							10120			10120		M	REMOVE AND RESET TEMPORARY TRAFFIC BARRIER	621.95	4			
			0.08	0.08				0.08		0.24		CM	INSULATION BOARD	622.10	-			
				7	7					14		M	DUCTILE IRON PIPE, CEMENT-LINED (150 mm) (CLASS 52)	628.28	-			
				22	82					104		M	DUCTILE IRON PIPE, CEMENT-LINED (200 mm) (CLASS 52)	628.28	-			
								8		8		M	PVC SEWER PIPE (100 mm)	628.35	-			
								4		4		M	PVC SEWER PIPE (150 mm)	628.35	-			
									14	14		M	PVC SEWER PIPE (200 mm) (AWWA C-900)	628.35	-			
								29	31	60		M	PVC SEWER PIPE (200 mm)	628.35	-			
				12	7					19		M	SEAMLESS COPPER WATER TUBE (25 mm)	629.23	-			
				1	1					2		EACH	EXTENSION SERVICE BOX AND CURB STOP (25 mm)	629.25	-			
				1	1					2		EACH	GATE VALVE WITH VALVE BOX (150 mm)	629.27	-			
				1						1		EACH	HYDRANT	629.28	-			
				1						1		EACH	REMOVE HYDRANT	629.30	-			
				1	1					2		EACH	CORPORATION STOP (25 mm)	629.39	-			
				22	55			23	26	126		T	CRUSHED STONE BEDDING	629.54	1.8			
2875							725			3600		HR	UNIFORMED TRAFFIC OFFICERS	630.10	25			
10450							300			10750		HR	FLAGGERS	630.15	37			
						1				1		LS	FIELD OFFICE, ENGINEERS	631.10	-			
						1				1		LS	TESTING EQUIPMENT, CONCRETE	631.16	-			
						1				1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17	-			
						1				1		LU	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.25	-			
	1560									1560		HR	EMPLOYEE TRAINEESHIP	634.10	-			
1										1		LS	MOBILIZATION/DEMOBILIZATION	635.11	-			
							1			1		LS	TRAFFIC CONTROL	641.10	-			
1										1		LS	PUBLIC RELATIONS OFFICER	641.12	-			
							4			4		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	-			
							8330			8330		M	100 MM WHITE LINE	646.20	2			
							8130			8130		M	100 MM YELLOW LINE	646.21	2			
							55			55		M	600 MM STOP BAR	646.26	-			
17										17		M	DURABLE 100 MM WHITE LINE	646.400	0.8			
9270										9270		M	DURABLE 100 MM WHITE LINE, THERMOPLASTIC	646.402	5			
8260										8260		M	DURABLE 100 MM YELLOW LINE, THERMOPLASTIC	646.412	6			
440										440		M	DURABLE 200 MM YELLOW LINE, THERMOPLASTIC	646.452	8			
55										55		M	DURABLE 600 MM STOP BAR, THERMOPLASTIC	646.482	3			
1										1		EACH	DURABLE LETTER OR SYMBOL	646.490	-			
87										87		EACH	DURABLE LETTER OR SYMBOL, THERMOPLASTIC	646.492	-			

PROJECT NAME: **BRANDON**
 PROJECT NUMBER: **NH 019-3(495)**
 FILE NAME: zb008_5qss1.xls PLOT DATE: 09/03/2009
 PROJECT LEADER: CRB DRAWN BY: NLL
 DESIGNED BY: PTS CHECKED BY: PTS
 QUANTITY SHEET #7 SHEET 11 OF 546