STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 9

Next Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	FLANGED CHANNEL kg/m 3.0	FLANGED CHANNEL kg/m 4.5	SQUARE STEEL (mm) 44 kg/m 3.4	SQUARE STEEL (mm) 50 kg/m 3.6	SQUARE STEEL (mm) 63 kg/m 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM DIA (mm) 75 kg/m 1.9	TUBULAR ALUMINUM DIA (mm) 100 kg/m 2.5	TUBULAR ALUMINUM DIA (mm) 100MOD kg/m 2.5	TUBULAR STEEL DIA (mm) FOUNDATION	TUBULAR STEEL DIA (mm) 75 kg/m 11.3	TUBULAR STEEL DIA (mm) 90 kg/m 13.6	TUBULAR STEEL DIA (mm) 100 kg/m 16.1	TUBULAR STEEL DIA (mm) 125 kg/m 21.8	W-SHAPE STEEL FTG. SIZE 600 mm	W-SHAPE STEEL FTG. SIZE 750 mm	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQ'D	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
NICKERSON RD 2+011 LT	NICKERSON RD	1					X				1					X		1															SALV SIGN TO BE INSTALLED ON TOP OF STOP SIGN		
	STOP 0070 1102 0291	1	750	750	0.56																												R1-1 BACK TO BACK		E-143
		1	150	250	0.04																														E-138
	← 905 907 →	1					X																												
2+021 RT	LEGAL LOAD LIMIT 24,000 POUNDS	1	600	750	0.45						1					X		1															VR-017		E-141
	SUBTOTAL SHEET 9				1.05	0.00	2	0.00			0	0	0.0	0	8.5	0		0	0	0	0	0	0	0	0	0	0	0	0	0	0				
	SUBTOTAL SHEET 1				6.78	0.00	0	0.00				0.0			51.0					0.0			0	0.0				0	0	0.0					
	SUBTOTAL SHEET 2				6.38	0.00	2	0.00				0.0			54.0					0.0			0	0.0				0	0	0.0					
	SUBTOTAL SHEET 3				4.42	0.00	0	0.00				0.0			37.5					0.0			0	0.0				0	0	0.0					
	SUBTOTAL SHEET 4				5.12	0.00	0	0.00				0.0			46.5					0.0			0	0.0				0	0	0.0					
	SUBTOTAL SHEET 5				1.92	0.00	3	1.44				0.0			30.5					0.0			0	0.0				0	0	0.0					
	SUBTOTAL SHEET 6				3.44	0.00	3	0.00				0.0			42.0					0.0			0	0.0				0	0	0.0					
	SUBTOTAL SHEET 7				4.52	0.00	2	2.16				0.0			42.0					0.0			0	0.0				0	0	0.0					
	SUBTOTAL SHEET 8				3.56	0.00	4	0.00				0.0			28.5					0.0			0	0.0				0	0	0.0					
	SUBTOTAL SHEET 9				1.05	0.00	2	0.00				0.0			8.5					0.0			0	0.0				0	0	0.0					
												m 0.0	m 0.0	m 0.0	m 0.0	m 0.0	m 0.0	EA. 0		kg 0.0	kg 0.0	kg 0.0		kg 0.0	kg 0.0	kg 0.0	kg 0.0								
	PROJECT TOTALS	m2 37.19	m2 0.00	EA. 16	m2 3.60							m 0.0			m 340.5					kg 0.0			EA. 0	kg 0.0				EA. 0	EA. 0	kg 0.0					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD.
POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND VTRANS "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: BRANDON
PROJECT NUMBER: NH 019-3(495)

FILE NAME:	02-0149TSSS.xls	PLOT DATE:	9/3/2009
PROJECT LEADER:	CRB	DRAWN BY:	HJC
DESIGNED BY:	NLL	CHECKED BY:	PTS
CLD REF. NO.:	02-0149	SHEET	278 OF 546