

# QUANTITY SHEET 3



SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
ROADWAY	TRAINING	LANDSCAPING	EROSION CONTROL	WATER	WATER - (NO FEDERAL/STATE)	FULL C.E. ITEMS	ROADWAY (TRAFFIC CONTROL)	SEWER	SEWER - (NO FEDERAL/STATE)	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
													BEGIN OPTION JJ					
80.9							9.1			90		M	750 CAAP 1.91 (68 X 12)	601.0236	-			
80.9							9.1			90		M	750 PCCSP 2.01 (68 X 12)	601.0436	-			
80.9							9.1			90		M	750 RCP CLASS III	601.0835	-			
80.9							9.1			90		M	750 CPEP(SL)	601.2625	-			
													END OPTION JJ					
													BEGIN OPTION KK					
31.5							4			35.5		M	750 CAAP 1.91 (68 X 12)	601.0236	-			
31.5							4			35.5		M	750 PCCSP 2.01 (68 X 12)	601.0436	-			
													END OPTION KK					
													BEGIN OPTION LL					
18.8										18.8		M	1050 CAAP 2.67 (68 X 12)	601.0252	-			
18.8										18.8		M	1050 PCCSP 2.77 (68 X 12)	601.0452	-			
													END OPTION LL					
													BEGIN OPTION MM					
60.3							4			64.3		M	1200 CAAP 2.67 (68 X 12)	601.0257	-			
60.3							4			64.3		M	1200 PCCSP 2.77 (68 X 12)	601.0457	-			
													END OPTION MM					
23.7										23.7		M	450 PCCSP 1.63 (68 X 12)	601.0415	-			
													BEGIN OPTION NN					
176.1										176.1		M	375 RCP CLASS III	601.0810	-			
176.1										176.1		M	375 CPEP(SL)	601.2610	-			
													END OPTION NN					
27.7							31.5			59.2		M	375 RCP CLASS IV	601.0811	-			
													BEGIN OPTION OO					
277.2							6.6			283.8		M	450 RCP CLASS III	601.0815	-			
277.2							6.6			283.8		M	450 CPEP(SL)	601.2615	-			
													END OPTION OO					
													BEGIN OPTION PP					
11.3										11.3		M	450 RCP CLASS IV	601.0816	-			
11.3										11.3		M	450 CPEP(SL)	601.2615	-			
													END OPTION PP					
64.7										64.7		M	525 RCP CLASS III	601.0820	-			
													BEGIN OPTION QQ					
167							11.8			178.8		M	600 RCP CLASS III	601.0825	-			
167							11.8			178.8		M	600 CPEP(SL)	601.2620	-			
													END OPTION QQ					
													BEGIN OPTION RR					
57.8										57.8		M	750 RCP CLASS III	601.0835	-			
57.8										57.8		M	750 CPEP(SL)	601.2625	-			

PROJECT NAME:	BRANDON
PROJECT NUMBER:	NH 019-3(495)
FILE NAME: zb008_5qss1.xls	PLOT DATE: 08/03/2009
PROJECT LEADER: CRB	DRAWN BY: NLL
DESIGNED BY: PTS	CHECKED BY: PTS
QUANTITY SHEET #3	SHEET 7 OF 546