STATE OF VERMONT
AGENCY OF TRANSPORTATION

ITEM DETAIL SHEET 2

Metric

CURB

BEGIN STATION	END STATION	POSITION		REMARKS
		LEFT	RIGHT	
km + m	km + m	m	m	

SIDEWALK

BEGIN STATION	END STATION	POSITION		REMARKS
		LEFT	RIGHT	
km + m	km + m	m^2	m^2	

GUARD RAIL

BEGIN STATION	END STATION	POSITION		END TREATMENT	
		LEFT	RIGHT	BEGIN	END
km + m	km + m	m	m	ea	ea

UNDERDRAIN

BEGIN STATION	END STATION	TYPE	POSITION	DIA.	LENGTH	TRENCH		GRAN BKFILL	FB	MKR PST
						EARTH	ROCK			
km + m	km + m			mm	m	m^3	m^3	m^3	ea	ea
US 7										
19+745	19+750	C	RT	200	7.4	7.4				
19+750	20+115	U	RT	200	365.0	253.7	114.4		3	3
19+760	19+766	C	LT	200	8.0	2.1	1.4			
19+766	19+845	U	LT	200	79.0	57.5	3.4		1	1
20+120	20+125	C	RT	200	6.3	6.6				
20+125	20+178	U	RT	200	53.0	55.1			1	1
20+180	20+185	C	RT	200	6.0	6.2				
20+185	20+320	U	RT	200	135.0	122.7	10.8		2	2
20+280	20+340	U	LT	200	60.0	56.1			1	1
20+324	20+330	C	RT	200	8.0	3.3				
20+330	20+550	U	RT	200	220.0	125.8	68.8		2	2
20+347	20+375	U	LT	200	28.0	17.9			1	1
20+550	20+780	U	LT	200	230.0	41.8	272.2		2	2
	SUBTOTAL SHEET 2	U		200	1170.0	756.2	471.0		13	13
	SUBTOTAL SHEET 2	C		200	35.7					
	TOTAL	**U**		**200**	**4345.0**	**3471.7**	**471.0**		**51**	**51**
	TOTAL	**C**		**200**	**247.2**					

zb008s5-1ds02.dgn

PROJECT NAME: BRANDON
PROJECT NUMBER: NH 019-3(495)

FILE NAME: zb008_5ids.xls
PROJECT LEADER: CRB
DESIGNED BY: PTS
ITEM DETAIL SHEET #2

PLOT DATE: 9/1/2009
DRAWN BY: JH
CHECKED BY: PTS