STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 1

Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) 44 kg/m 3.4	50 kg/m 3.6	63 kg/m 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM DIA (mm) 75 kg/m 1.9	100 kg/m 2.5	100MOD kg/m 2.5	TUBULAR STEEL DIA (mm) FOUNDATION	75 kg/m 11.3	90 kg/m 13.6	100 kg/m 16.1	125 kg/m 21.8	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAME REQ'D	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
US 7 16+241 RT	8-24-10	1	900	900	0.81						2					X 4.6 4.1		2																S1-1 FLUORESCENT YELLOW-GREEN SHEETING		E-153
	AHEAD 8-24-10	1	~~600~~ 900	~~300~~ 600	~~0.18~~ 0.54																												W16-9p FLUORESCENT YELLOW-GREEN SHEETING	241	
16+303 RT	SCHOOL 8-24-10	1	600	200	0.12						1					X		1															W/FLASHING BEACON S4-3 FLUORESCENT YELLOW-GREEN SHEETING		E-153
	SPEED LIMIT 40 8-24-10	1	600	750	0.45						1							1															R2-1		E-142
	WHEN FLASHING 8-24-10	1	600	250	0.15						1							1															S4-4		E-153
16+386 RT	DO NOT PASS 8-24-10	1	600	750	0.45						1					X 4.3		1															R4-1		E-141
16+431 LT	DO NOT PASS 8-24-10	1	600	750	0.45						1					X 4.6		1															R4-1		E-141
16+468 LT	STOP / DO NOT ENTER 8-24-10	1 1	750 750	750 750	0.56 0.56						1					X 4.1		1															R1-1 BACK TO BACK R5-1		E-143 E-143
16+481 LT	STOP / DO NOT ENTER 8-24-10	1 1	750 750	750 750	0.56 0.56						1					X 4.1		1															R1-1 BACK TO BACK R5-1		E-143 E-143
16+586 RT	ONLY 8-24-10	1	750	750	0.56						1					X 4.3		1															VR-921		E-145A
16+630 LT	DO NOT PASS 11-22-10	1	600	750	0.45						1					X 4.5		1															R4-1		E-141
16+640 RT	OTTER VALLEY UNION ← HIGH SCHOOL 8-24-10	1	1830	500	0.92						2					X 4.4 4.2		2															D1-2(L)		E-123
											m 0.0	m 0.0	m 0.0	m 0.0	m 51.0 43.3	m 0.0 4.9		EA. 0	kg 0.0	kg 0.0	kg 0.0		kg 0.0	kg 0.0	kg 0.0	kg 0.0	EA. 0	EA. 0	kg 0					
SHEET TOTALS		m2 ~~6.78~~ 7.14	m2 0.00	EA. 0	m2 0.00				m 0.0						m ~~51.0~~ 48.1				kg 0.0			EA. 0	kg 0.0				EA. 0	EA. 0	kg 0					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND VTRANS "SIGN POST DESIGN GUIDELINE".

To Sign Summary Sheet #9 JB 7-7-11

To Sign Summary Sheet #9 JB 7-7-11

PROJECT NAME: BRANDON
PROJECT NUMBER: NH 019-3(495)

FILE NAME:	02-0149TSSS.xls	PLOT DATE:	9/3/2009
PROJECT LEADER:	CRB	DRAWN BY:	HJC
DESIGNED BY:	NLL	CHECKED BY:	PTS
CLD REF. NO.:	02-0149	SHEET	270 OF 546