STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 3

Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) 44 50 63 kg/m 3.4	3.6	5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM DIA (mm) 75 100 100MOD kg/m 1.9	2.5	2.5	TUBULAR STEEL DIA (mm) FOUNDATION 75 90 100 125 kg/m 11.3	13.6	16.1	21.8	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAMED FREQ'D	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
US 7																																		
17+013 LT	0070 1102 0100 11-29-10	1	150	250	0.04						1				X 2.41			1																E-138
17+053 LT	SCHOOL 11-29-10	1	600	200	0.12						1					~~X~~	5.1	1														S4-3 W/FLASHING BEACON FLUORESCENT YELLOW-GREEN SHEETING		E-153
	SPEED LIMIT 40 11-29-10	1	600	750	0.45																											R2-1		E-142
	WHEN FLASHING 11-29-10	1	600	250	0.15																											S4-4		E-153
17+055 RT	SPEED LIMIT 50 11-22-10	1	600	750	0.45						1				X 5.0			1															R2-1		E-142
	END SCHOOL ZONE 11-22-10	1	600	750	0.45																											S5-2	241	
17+115 LT	11-29-10	1	900	900	0.81						2				X 4.3 4.3			2															S1-1 FLUORESCENT YELLOW-GREEN SHEETING		E-153
	AHEAD 11-29-10	1	~~600~~ 900	~~300~~ 600	0.18 0.54																											W16-9P FLUORESCENT YELLOW-GREEN SHEETING	241	
17+298 LT	11-29-10	1	750	750	0.56						1				X 4.5			1															W11-3	241	
	NEXT 2 MI 11-29-10	1	600	450	0.27																											W7-3a		E-152
17+336 LT	0070 1102 0120 11-29-10	1	150	250	0.04						1				X 2.2			1																	E-138
17+362 LT	DO NOT PASS 11-29-10	1	600	750	0.45						1					X 4.0		1															R4-1		E-141
17+435 LT	SPEED LIMIT 50 11-29-10	1	600	750	0.45						1					X 4.1		1															R2-1		E-142
												m 0.0	m 0.0	m 0.0	m ~~6.5~~ 4.6	m ~~31.0~~ 26.2	m ~~0.0~~ 5.1		EA. 0	kg 0.0	kg 0.0	kg 0.0		kg 0.0	kg 0.0	kg 0.0	kg 0.0							
	SHEET TOTALS		m2 ~~4.79~~ 4.42	m2 0.00	EA. 0	m2 0.00						m 0.0			m ~~37.5~~ 35.9					kg 0.0	EA. 0	kg 0.0		EA. 0	EA. 0	kg 0								

To Sign Summary Sheet #9 3B 7-7-11

To Sign Summary Sheet #9 3B 7-7-11

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND VTRANS "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: BRANDON
PROJECT NUMBER: NH 019-3(495)

FILE NAME:	02-0149TSSS.xls	PLOT DATE:	9/3/2009
PROJECT LEADER:	CRB	DRAWN BY:	HJC
DESIGNED BY:	NLL	CHECKED BY:	PTS
CLD REF. NO.:	02-0149	SHEET	272 OF 546