

QUANTITY SHEET

SUMMARY OF ESTIMATED QUANTITIES													TOTALS			DESCRIPTIONS			DETAILED SUMMARY OF QUANTITIES		
													ROUND	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	QUANTITIES	UNIT	ITEMS
													25	650		CY	COMMON EXCAVATION	203.15	131	TON	4" Type I
													15	425		CY	SAND BORROW	203.31	171	TON	3" Type II
													21	1250		SY	FINE GRADING-SUBGRADE	203.40	813	TON	2" Type III
													22	7325		SY	COLD PLANING-BIT.PAVEMENT	210.10	20	TON	Mountable Apron
													32	700		CY	SUBBASE OF DENSE GRADED CRUSHED STONE	301.35	6	TON	Traffic Island
														30		CWT	EMULSIFIED ASPHALT	404.65	1141	TON	Subtotal
													9	1150		TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT (PG-64-28)	490.30	9	TON	Rounding
														25		HR	BULLDOZER RENTAL, TYPE I	608.10	1150	TON	TOTAL
														25		HR	POWER BROOM RENTAL	608.30			
														25		HR	TRUCK RENTAL	608.37			
														25		HR	LOADER RENTAL, TYPE I	608.40			
														50		MGAL	DUST CONTROL WITH WATER	609.10			
														2		TON	DUST AND ICE CONTROL WITH CALCIUM CHLORIDE	609.15			
														20		CY	STONE FILL, TYPE I (MOD. - CHECK DAM)	613.10			
														15		CY	STONE FILL, TYPE I (MOD. - INLET PROTECTION)	613.10			
														206	4	LF	GRANITE SLOPE EDGING	616.20			
														4		TON	BIT. CONC. GUTTERS & TRAFFIC ISLANDS	616.47			
														638		LF	STEEL BEAM GUARD RAIL (GALVANIZED)	621.20			
														1		EACH	MANUFACTURED TERMINAL SECTION (TANGENT)	621.505			
														4		EACH	TRAILING END TERMINAL	621.52			
														2		EACH	ANCHOR FOR STEEL BEAM RAIL	621.60			
														1000		HR	UNIFORMED TRAFFIC OFFICERS	630.10			
														1000		HR	FLAGGERS	630.15			
														1		LS	TESTING EQUIPMENT - BITUMINOUS (MOD.)	631.17			
														1		LS	MOBILIZATION / DEMOBILIZATION	635.11			
														1		LS	TRAFFIC CONTROL	641.10			
														3		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15			
														2382	18	LF	DURABLE 4" WHITE LINE (THERMOPLASTIC)	646.40			
														1368	32	LF	DURABLE 4" YELLOW LINE (THERMOPLASTIC)	646.41			
														274	26	LF	DURABLE 8" YELLOW LINE (THERMOPLASTIC)	646.43			
														210	40	LF	DURABLE 12" WHITE LINE (THERMOPLASTIC)	646.44			
														112	8	LF	DURABLE 24" STOP BAR (THERMOPLASTIC)	646.46			
														25		EACH	DURABLE LETTER OR SYMBOL (THERMOPLASTIC)	646.50			
														2382	18	LF	TEMPORARY 4" WHITE LINE (PAINT)	646.60			
														1368	32	LF	TEMPORARY 4" YELLOW LINE (PAINT)	646.61			
														210	40	LF	TEMPORARY 8" YELLOW LINE (PAINT)	646.63			
														274	26	LF	TEMPORARY 12" WHITE LINE (PAINT)	646.64			
														112	8	LF	TEMPORARY 24" STOP BAR (PAINT)	646.66			
														25		EACH	TEMPORARY LETTERS OR SYMBOLS (PAINT)	646.70			
														100		EACH	LINE STRIPING TARGETS	646.76			

PROJECT NAME: **Clarendon**
PROJECT NUMBER: **NHG SGNL (24)**
FILE NAME: _____ PLOT DATE: **02/28/2005**
PROJECT MANAGER: **nyquist** DRAWN BY: _____
DESIGNED BY: **gruchacz** CHECKED BY: _____
QUANTITY SHEET #1 SHEET **4** OF **37**