STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET #2

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	2.0 2.16	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	FOUNDATION	TUBULAR STEEL Ø (in) lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
											OPTION ITEMS																									
STA 105+43 LT	1360 1418 0180	1	6	10	0.42						1				X																				E-138
STA 111+50 LT		1	30	30	6.25						1					X																		WI-2R		E-151
STA 115+99 RT	1360 1418 0200	1	6	10	0.42						1				X																				E-138
STA 126+55 LT	1360 1418 0220	1	6	10	0.42						1				X																				E-138
STA 129+61 LT	SPEED LIMIT 35	1	24	30	5.00						1					X																		R2-1		E-142
STA 131+61 LT	WEST 143	1 1	24 30	12 24	2.00 5.00						1					X																		M3-4		E-136C E-136C
STA 132+32 LT	EUREKA RD STOP 1360 1418 0230	1 1	30 6	30 10	6.25 0.42		1				1					X																		RI-1		E-143 E-138
STA 133+61 RT	EAST 143	1 1	24 30	12 24	2.00 5.00						1					X																		M3-2		E-136C E-136C
STA 135+61 RT	SPEED LIMIT 35	1	24	30	5.00						1					X																		R2-1		E-142
STA 136+68 LT	25 M.P.H. 1360 1418 0240	1 1 1	30 18 6	30 18 10	6.25 2.25 0.42						1					X																		WI-1Ma L WI3-1	67	 E-138
STA 137+50 RT		1	30	30	6.25						1					X																		WI-2L		
STA 140+89 LT	SPEED LIMIT 35	1	24	30	5.00						1					X																		R2-1		E-142
STA 142+89 LT	WEST 143	1 1	24 30	12 24	2.00 5.00						1					X																		M3-4		E-136C E-136C
STA 143+78 RT	CROWN POINT RD STOP	1	30	30	6.25		1				1					X																		RI-1		E-143
STA 144+18 RT	STOP 1360 1418 0252	1 1	30 6	30 10	6.25 0.42						1					X																		RI-1		E-143 E-138
												FT	FT	FT	FT 21	FT 180	FT		EA	LB	LB	LB		LB	LB	LB	LB								
TOTALS					SF 78.27	SF	EA. 2	EA				FT			FT 201					LB			EA.	LB				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND VTRANS DIVISION'S "SIGN POST DESIGN GUIDELINE."

SEE SPECIAL PROVISIONS FOR ADDITIONAL SIGN INFORMATION

TRAFFIC SIGN SUMMARY SHEET 2

PROJECT NAME: SPRINGFIELD
PROJECT NUMBER: STP 0136(I)

FILE NAME: ...02c084\...02c084_frm.dgn
PROJECT LEADER: K. UPMAL
DESIGNED BY: B. KIPP\N. PAPPAS
IPARM FILE NAME: 02c084_tss_02

PLOT DATE: 30-DEC-2008
DRAWN BY: B. KIPP\N. PAPPAS
CHECKED BY: N. PAPPAS
SHEET 62 OF 68