STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET #3

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (in)	SIGN DIMENSIONS HEIGHT (in)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) lb/ft 1.75	SQUARE STEEL (in) lb/ft 2.0	SQUARE STEEL (in) lb/ft 2.5	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0	TUBULAR ALUMINUM Ø (in) lb/ft 4.0	TUBULAR ALUMINUM Ø (in) lb/ft 4.0 MOD	TUBULAR STEEL Ø (in) FOUND-ATION	TUBULAR STEEL Ø (in) lb/ft 3.0	TUBULAR STEEL Ø (in) lb/ft 3.5	TUBULAR STEEL Ø (in) lb/ft 4.0	TUBULAR STEEL Ø (in) lb/ft 5.0	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
												OPTION ITEMS																							
STA 144+75 RT	EAST 143	1 1	24 30	12 24	2.00 5.00						1					X																	M3-2		E-136C E-136C
STA 144+78 LT		1	30	30	6.25						1					X																	WI-2R		E-151
STA 146+75 RT	SPEED LIMIT 35	1	24	30	5.00						1					X																	R2-1		E-142
STA 147+67 RT	1360 1418 0260	1	6	10	0.42						1				X																				E-138
STA 148+75 RT		1	30	30	6.25						1					X																	WI-2R		
STA 152+90 LT		1	30	30	6.25						1					X																	WI-2L		
STA 158+23 LT	1360 1418 0280	1	6	10	0.42										X																				E-138
STA 161+54 RT		1 1	48 48	24 24	8.00 8.00						2					X																	WI-6 WI-6		E-152
STA 168+79 RT	1360 1418 0300	1	6	10	0.42						1				X																				E-138
STA 171+75 LT	SPEED LIMIT 35	1	24	30	5.00						1					X																	R2-1		E-142
STA 176+22 LT	WEST 143	1 1	24 30	12 24	2.00 5.00						1					X																	M3-4		E-136C E-136C
STA 176+98 RT	SPENCER HOLLOW RD STOP 1360 1418 0318	1 1	30 6	30 10	6.25 0.42		1				1					X																	RI-1		E-143 E-138
STA 177+88 RT	STOP 1360 1418 0318	1 1	30 6	30 10	6.25 0.42						1					X																	RI-1		E-143 E-138
TOTALS					SF 73.35	SF	EA. 1	EA				FT	FT	FT	FT 21	FT 165	FT		EA	LB	LB	LB		LB	LB	LB	LB								
												FT			FT 186					LB			EA.	LB				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND VTRANS DIVISION'S "SIGN POST DESIGN GUIDELINE."

SEE SPECIAL PROVISIONS FOR ADDITIONAL SIGN INFORMATION

TRAFFIC SIGN SUMMARY SHEET 3

PROJECT NAME: SPRINGFIELD
PROJECT NUMBER: STP 0136(1)

FILE NAME: ...02c084\...02c084_frm.dgn
PROJECT LEADER: K. UPMAL
DESIGNED BY: B. KIPP\N. PAPPAS
IPARM FILE NAME: 02c084_tss_03

PLOT DATE: 30-DEC-2008
DRAWN BY: B. KIPP\N. PAPPAS
CHECKED BY: N. PAPPAS
SHEET 63 OF 68