STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 3.4	50 3.9	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	TUBULAR STEEL Ø (mm) FOUNDATION	kg/m 75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	WEIGHT	POST SIZE	SIGN FRAMED REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																								
1+156.500 LT		1	750	750	0.563		X				1		X 4.27 M																				EXISTING SIGNS DAMAGED		
1+156.500 LT	AHEAD	1	300	600	0.180		X																												
1+163.000 RT	SOUTH	1	600	300	0.180						1		X 4.27 M																				M 3 - 3		E-136BM
1+163.000 RT	VERMONT 12	1	600	600	0.360																												M 1 - 5		E-136BM
1+163.000 RT		1	525	375	0.197																												M 6 - 1		E-136BM
1+255.500 RT	SPEED LIMIT 25	1					1				1		X 3.96 M																						
1+239.500 LT	NORTH	1	600	300	0.180						1		X 4.27 M																				M 3 - 1		E-136BM
1+239.500 LT	VERMONT 12	1	600	600	0.360																												M 1 - 5		E-136BM
1+239.500 LT		1	525	375	0.197																												M 6 - 1		E-136BM
1+240.000 LT	N MAIN ST	1					1				1		X 3.35 M																						
1+240.500 LT	STOP	1	750	750	0.563						1		X 3.96 M																				R 1 - 1		E-143M
1+256.000 LT	SOUTH	1	600	300	0.180						1		X 4.27 M																				M 3 - 3		E-136BM
1+256.000 LT	VERMONT 12	1	600	600	0.360																												M 1 - 5		E-136BM
1+256.000 LT		1	525	375	0.197																												M 6 - 1		E-136BM
1+260.000 LT	NORTH	1	600	300	0.180						1		X 4.27 M																				M 3 - 1		E-136BM
1+260.000 LT	VERMONT 12	1	600	600	0.360																												M 1 - 5		E-136BM
1+260.000 LT		1	525	375	0.197																												M 6 - 1		E-136BM
												m	m ~~29.50~~ 32.62	m	m	m	m		EA	kg	kg	kg		kg	kg	kg	kg								
TOTALS					m² ~~3.50~~ 4.254	m²	EA. ~~4~~ 2	m²				m ~~29.50~~ 32.62			m					kg			EA.	kg				EA.	EA.	kg					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: BETHEL
PROJECT NUMBER: BRF 0241(33) C/2

FILE NAME: sc180tsst.i
PROJECT LEADER: C.P.WILLIAMS
DESIGNED BY: K.M. HIGGINS
TRAFFIC SIGN SUMMARY SHEET 1

PLOT DATE: 15-APR-2005
DRAWN BY: T. ANDERSON
CHECKED BY: K.M. HIGGINS
SHEET 21 OF 130