

QUANTITY SHEET - STP 0126(4)S



SUMMARY OF ESTIMATED QUANTITIES							
EROSION CONTROL	WALL #3	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	UNIT NUMBER	RND
-	-	1	1	LS	TESTING EQUIPMENT - BITUMINOUS	631.17	-
-	-	1	1	LU	FIELD OFFICE TELEPHONE NOT A BID ITEM	631.25	-
-	-	1	1	LS	MOBILIZATION	635.10	-
-	-	1	1	LS	TRAFFIC CONTROL	641.10	-
-	-	5,700	5,700	M	100 mm WHITE LINE	646.20	-
-	-	6,200	6,200	M	DURABLE 100 mm YELLOW LINES	646.41	-
-	-	30	30	M	DURABLE 600 mm STOP BARS	646.46	-
-	-	2,600	2,600	M	TEMPORARY 100 mm WHITE LINES	646.60	-
-	-	2,600	2,600	M	TEMPORARY 100 mm YELLOW LINE	646.61	-
-	-	400	400	EA	LINE STRIPING TARGETS	646.76	-
-	-	990	990	SM	GEOTEXTILE UNDER STONE FILL	649.31	-
-	-	13,800	13,800	SM	GEOTEXTILE UNDER STONE FILL (MOD - GEOTEXTILE FOR STEEP SLOPES)	649.31	-
400	-	3,800	4,200	SM	GEOTEXTILE FOR SILT FENCE	649.51	-
-	-	250	250	KG	SEEDING	651.15	-
-	-	0.5	0.5	KG	WILDFLOWER SEED	651.16	-
5	-	50	55	KG	WINTER RYE	651.17	-
-	-	1,800	1,800	KG	FERTILIZER	651.18	EST
-	-	16	16	TON	AGRICULTURAL LIMESTONE	651.20	-
-	-	15	15	TON	HAY MULCH	651.25	-
130	-	1,300	1,430	EA	HAY BALES FOR EROSION CONTROL	651.26	-
-	-	1,600	1,600	CM	TOPSOIL	651.35	-
1	-	-	1	LS	EROSION AND SEDIMENT CONTROL PLAN	652.10	-
120	-	-	120	HR	MONITORING EROSION AND SEDIMENT CONTROL PLAN	652.20	EST
1	-	-	1	LU	FIELD MAINTENANCE OF EROSION AND SED. CONTROL PLAN NOT A BID ITEM	652.30	-
-	-	1,700	1,700	SM	EROSION MATTING	654.10	-
-	-	35	35	EA	EVERGREEN TREES	656.20	-
-	-	30	30	EA	DECIDUOUS TREES	656.30	-
-	-	115	115	EA	DECIDUOUS SHRUBS	656.35	-
-	-	300	300	EA	DECIDUOUS SHRUBS (MOD-WETLAND BUFFER SHRUBS)	656.35	-
-	-	230	230	EA	GROUND COVER AND VINES (MOD - LIVE STAKES)	656.40	-
-	-	130	130	EA	GROUND COVER AND VINES (MOD - FASCINES)	656.40	-
-	-	3,210	3,210	EA	GROUND COVER AND VINES (MOD - NATIVE WILLOW CUTTINGS)	656.40	-
-	-	10	10	EA	TRANSPLANTING SHRUBS	656.50	-
-	-	13	13	SM	TRAFFIC SIGNS (TYPE A)	675.20	-
-	-	630	630	KG	FLANGED CHANNEL SIGN POSTS	675.30	-

SUMMARY OF ESTIMATED QUANTITIES							
EROSION CONTROL	WALL #3	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	UNIT NUMBER	RND
-	-	20	20	EA	REMOVING SIGNS	675.50	-
-	-	10	10	EA	ERECTING SALVAGED SIGNS	675.60	-
-	-	75	75	EA	DELINEATOR W/STEEL POSTS	676.10	-

DATUM
 VERTICAL NGVD 1929
 HORIZONTAL NAD 1927

V:\1261\CADD\PLANS\SUMMARY_SHEET_C2.DWG



THE LOUIS BERGER GROUP, INC.

PROJECT: GRAFTON-ROCKINGHAM, ROUTE 121	PROJECT NO. : STP 0126(4)S
DESIGN FILE NAME: IPARM FILE NAME: SURVEYED BY: SQUAD LEADER:	PLOT DATE: 12/08/03 SURVEY DATE: DRAWN BY: SHEET: 3 OF 116