

QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
						ROADWAY	LANDSCAPING	EROSION CONTROL	UTILITIES - BID ITEMS	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
						1					1		LS	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS	201.10				
						1450					1450		CY	COMMON EXCAVATION	203.15	108			
						30					30		CY	SOLID ROCK EXCAVATION	203.16				
						350					350		CY	EARTH BORROW	203.30	32.44			
						220					220		CY	TRENCH EXCAVATION OF EARTH	204.20	25.56			
						20					20		CY	TRENCH EXCAVATION OF ROCK	204.21				
						1					1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22				
						1600					1600		CY	SUBBASE OF DENSE GRADED CRUSHED STONE	301.35	73.95			
						25					25		CWT	EMULSIFIED ASPHALT	404.65	1.19			
						1					1		LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50				
						825					825		TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT	490.30	26.52			
						270					270		LB	REINFORCING STEEL, LEVEL I	507.11	2.47			
						8					8		GAL	WATER REPELLENT, SLANE	514.10	1.59			
						4					4		CY	CONCRETE, CLASS B	541.25	0.6			
						10					10		LF	PRECAST REINFORCED CONCRETE CURB, TYPE B	618.26	1			
						80					80		SY	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	618.10	3.24			
						8					8		EACH	YIELDING MARKER POSTS	619.17				
						1					1		EACH	REMOVING AND RESETTING PROPERTY MARKERS	619.20				
						225					225		LF	WOVEN WIRE FENCE WITH STEEL POSTS	620.25	2.56			
						1					1		EACH	DRIVE GATE FOR WOVEN WIRE FENCE	620.30				
						6					6		EACH	STEEL BRACE FOR WOVEN WIRE FENCE	620.40				
						125					125		LF	REMOVING AND RESETTING FENCE	620.50	1.42			
						50					50		LF	PLANK RAIL	621.15				
						18					18		EACH	REMOVAL AND DISPOSAL OF GUIDE POSTS	621.81	2			
						80					80		HR	FLAGGERS	630.15				
										1	1		LS	FIELD OFFICE, ENGINEERS	631.10				
										1	1		LS	TESTING EQUIPMENT, CONCRETE	631.16				
										1	1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17				
										3000	3000		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26				
						1					1		LS	MOBILIZATION/DEMOBILIZATION	635.11				
						1					1		LS	TRAFFIC CONTROL	641.10				
						2500					2500		LF	DURABLE 4 INCH WHITE LINE	646.400	65.6			
						130					130		LF	DURABLE 4 INCH YELLOW LINE	646.410	3.8			
						20					20		LF	DURABLE 24 INCH STOP BAR	646.480				
						7					7		EACH	DURABLE LETTER OR SYMBOL	646.490				
								2200			2200		SY	GEOTEXTILE FOR ROADBED SEPARATOR	649.11	28.76			
								200			200		SY	GEOTEXTILE FOR SILT FENCE	649.51	16.6			
								50			50		LB	SEED	651.15	4.44			
								90			90		LB	FERTILIZER	651.18	2.84			
								0.5			0.5		TON	AGRICULTURAL LIMESTONE	651.20	0.15			

PROJECT NAME:	Hartland Park and Ride
PROJECT NUMBER:	CMG Park (25)
FILE NAME:	Z02K154quantity
PROJECT MANAGER:	WLD
DESIGNED BY:	JCC
QUANTITY SHEET #1	
PLOT DATE:	09/17/2013
DRAWN BY:	AGB
CHECKED BY:	CRM
SHEET	4 OF 30

8/17/2013 2:05:12 PM C:\Users\jcc\Documents\CMG\25\154\quantity.sp