QUANTITY SHEET

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
500	500	SY	COLD PLANING - BITUMINOUS PAVEMENT	210.10	11
30	30	Ton	SUBBASE OF CRUSHED GRAVEL (FINE GRADED)	301.28	EST.
60	60	Ton	AGGREGATE SHOULDER MATERIAL	402.12	
12	12	CWT	EMULSIFIED ASPHALT	404.65	
800	800	Ton	BITUMINOUS CONCRETE PAVEMENT (PG 64-28)	406.25	
15	15	HR	POWER BROOM RENTAL, TYPE II	608.31	
25	25	HR	TRUCK RENTAL	608.37	
25	25	HR	LOADER RENTAL, TYPE I	608.40	
100	100	HR	UNIFORMED TRAFFIC OFFICERS	630.10	
150	150	HR	FLAGGERS	630.15	
1	1	LS	TESTING EQUIPMENT - BITUMINOUS (MOD)	631.17	
1	1	LS	MOBILIZATION	635.10	
1	1	LS	TRAFFIC CONTROL	641.10	
3	3	EA	PORTABLE ARROW BOARD	641.15	
4595	4595	LF	DURABLE 4" WHITE LINE	646.40	
3090	3090	LF	DURABLE 4" YELLOW LINE	646.41	
86	86	LF	DURABLE 24" STOPBAR	646.46	
24	24	EA	DURABLE LETTERS OR SYMBOLS	646.50	
200	200	EA	LINE STRIPING TARGETS	646.76	
20	20	LB	SEED	651.15	
15	15	SF	TRAFFIC SIGNS, TYPE A	675.20	
28	28	LF	SQUARE TUBE SIGN POSTS AND ANCHOR	675.341	
530	530	LF	VEHICLE LOOP DETECTOR	678.22	
30	30	LF	WIRED CONDUIT (2" PVC)	678.23	

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
785	Ton	BITUMINOUS CONCRETE PAVEMENT (TYPE III) TOP

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT NAME: CHARLOTTE
PROJECT NUMBER: HES 019-4(30)

FILE NAME: _____ PLOT DATE: 23-AUG-2004
PROJECT LEADER: AMY GAMBLE DRAWN BY: _____
DESIGNED BY: _____ CHECKED BY: _____
SHEET 3 OF 6