STATE OF VERMONT
AGENCY OF TRANSPORTATION

QUANTITY SHEET

VAOT Metric

SUMMARY OF ESTIMATED QUANTITIES

						EMPLOYEE TRAINEESHIP	EROSION CONTROL	BRIDGE'S 800	BRIDGE'S 1100	BRIDGE'S 1200	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NUMBER	RND
						-	-	248	307	268	-	823	m	REMOVAL OF EXISTING RAIL	525.10	-
						-	-	248	307	268	-	823	m	BRIDGE RAILING - NETC - 2 RAIL	525.33	-
						-	-	1801	1949	1749	-	5499	m^2	REMOVAL OF BRIDGE PAVEMENT	529.10	-
						-	-	-	2	2	-	4	EA	PARTIAL REMOVAL OF STRUCTURE	529.20	-
						-	-	44	54	48	-	146	m^3	REMOVAL OF CONCRETE OR MASONRY	529.25	-
						-	-	-	24	36	-	60	EA	BEARING DEVICE ASSEMBLY (STEEL LAMINATED ELASTOMERIC)	531.10	-
						-	-	30	24	30	-	84	m^2	REPAIR OF CONCRETE SUPERSTRUCTURE SURFACE - CLASS I	580.10	-
						-	-	20	20	20	-	60	m^2	REPAIR OF CONCRETE SUPERSTRUCTURE SURFACE - CLASS II	580.11	-
						-	-	20	20	20	-	60	m^3	REPAIR OF CONCRETE SUPERSTRUCTURE SURFACE - CLASS III	580.12	-
						-	-	74	60	72	-	206	m^2	SURFACE PREPARATION FOR MEMBRANE	580.16	-
						-	-	2	2	2	-	6	m^3	RAPID SETTING CONCRETE REPAIR MATERIAL	580.17	-
						-	-	-	-	-	16	16	EA	CHANGE ELEVATION OF DI, CB, OR MH	604.40	-
						-	-	-	-	-	40	40	HR	ALL- PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	EST.
						-	-	-	-	-	30	30	HR	POWER BROOM RENTAL	608.30	EST.
						-	-	-	-	-	60	60	HR	TRUCK RENTAL	608.37	EST.
						-	8	-	-	-	-	8	m^3	STONE FILL, TYPE I	613.10	0.8
						-	-	-	-	2	-	2	m^2	SLOPE PAVING	613.20	3.5
						-	-	-	-	-	180	180	m	CAST - IN - PLACE CONCRETE CURB, TYPE B	616.28	3.2
						-	-	-	-	-	51	51	t	BITUMINOUS CONCRETE CURB, TYPE B	616.31	0.7
						-	-	-	-	-	7	7	EA	YIELDING MARKER POSTS	619.17	-
						-	-	100	-	64	-	164	m	SNOW BARRIER (GALVANIZED)	620.75	-
						-	-	-	-	-	2056.6	2056.6	m	STEEL BEAM GUARDRAIL	621.20	-
						-	-	-	-	-	8	8	EA	MANUFACTURED TERMINAL SECTION (FLARED)	621.505	-
						-	-	-	-	-	6	6	EA	TRAILING END TERMINAL	621.52	-
						-	-	-	-	-	16	16	EA	GUARDRAIL APPROACH SECTION, NETC 2 RAIL (MOD.)	621.72	-
						-	-	-	-	-	1927.6	1927.6	m	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80	-
						-	-	-	-	-	150	150	m	TEMPORARY TRAFFIC BARRIER	621.90	EST.

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT:	PROJECT NO.:
BENNINGTON - HOOSICK	D.P.I. 0146(1) C/6
DESIGN FILE NAME: QUAN.DGN	
IPARM FILE NAME: N/A	PLOT DATE: 2/04
SURVEYED BY: N/A	SURVEY DATE: N/A
SQUAD LEADER: T.P.K.	DRAWN BY: E.C.D.
DWG. NO. Q-2	SHEET: 7 OF 83

FILE NAME =u:\5116\VAOT\CONTRACT6\quan.dgn
DATE/TIME =2/16/2004
USER =2225