STATE OF VERMONT
AGENCY OF TRANSPORTATION

QUANTITY SHEET

VAOT Metric

SUMMARY OF ESTIMATED QUANTITIES

						EMPLOYEE TRAINEESHIP	EROSION CONTROL	BRIDGE'S 800	BRIDGE'S 1100	BRIDGE'S 1200	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NUMBER	RND
						-	-	-	-	-	16.74	16.74	m^2	TRAFFIC SIGNS, TYPE A	675.20	-
						-	-	-	-	-	81.54	81.54	m^2	TRAFFIC SIGNS, TYPE B	675.21	-
						-	-	-	-	-	1535	1535	kg	W - SHAPE STEEL SIGN POSTS	675.31	-
						-	-	-	-	-	31.5	31.5	kg	TUBULAR ALUMINUM SIGN POSTS	675.32	-
						-	-	-	-	-	126.5	126.5	m	SQUARE TUBE SIGN POSTS AND ANCHOR	675.341	-
						-	-	-	-	-	2	2	EA	FOUNDATION FOR W - SHAPE STEEL POSTS, 600 mm DIAMETER	675.41	-
						-	-	-	-	-	3	3	EA	FOUNDATION FOR W - SHAPE STEEL POSTS, 750 mm DIAMETER	675.42	-
						-	-	-	-	-	22	22	EA	REMOVING SIGNS	675.50	-
						-	-	-	-	-	160	160	EA	DELINEATOR WITH STEEL POSTS	676.10	-
						-	-	-	-	-	1	1	EA	OVERHEAD TRAFFIC SIGN SUPPORT, CANTILEVER	677.12	-

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT: BENNINGTON - HOOSICK	PROJECT NO.: D.P.I. 0146(1) C/6
DESIGN FILE NAME: QUAN.DGN	
IPARM FILE NAME: N/A	PLOT DATE: 2/04
SURVEYED BY: N/A	SURVEY DATE: N/A
SQUAD LEADER: T.P.K.	DRAWN BY: E.C.D.
DWG. NO. Q-4	SHEET: 9 OF 83

FILE NAME =z:\5116\VAOT\CONTRACT6\quan.dgn
DATE/TIME = 2/16/2004
USER = 2225