STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (mm)	SIGN DIMENSIONS HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	FLANGED CHANNEL kg/m 3.0	FLANGED CHANNEL kg/m 4.5	SQUARE STEEL (mm) kg/m 44 2.8	SQUARE STEEL (mm) kg/m 50 3.2	SQUARE STEEL (mm) kg/m 63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	TUBULAR ALUMINUM Ø (mm) kg/m 100 2.5	TUBULAR ALUMINUM Ø (mm) kg/m 100 MOD 2.5	TUBULAR STEEL Ø (mm) FOUND-ATION	TUBULAR STEEL Ø (mm) kg/m 75 11.3	TUBULAR STEEL Ø (mm) kg/m 89 13.4	TUBULAR STEEL Ø (mm) kg/m 100 16.1	TUBULAR STEEL Ø (mm) kg/m 125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	W-SHAPE STEEL FTG. SIZE 750 mm	W-SHAPE STEEL MASS	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
VT. ROUTE 279 D.P.I. 0146(1) C/3 14+118.0. RT	BRIDGE 1 VT 279	1	150	200	0.03						1				X			X																ESIGN ID CODE VD-7013		E-134M
X10+040 RT OH	VERMONT 279 TO 7 BENNINGTON DOWNTOWN MANCHESTER	1	5500	3900		21.65																												INSTALLED ON EXISTING SUPPORTS	SECTION 7	
14+187.0, LT	BRIDGE 1 VT 279	1	150	200	0.03						1				X			X																ESIGN ID CODE VD-7013		E-134M
14+851.0. RT	BRIDGE 2 VT 279	1	150	200	0.03						1				X			X																ESIGN ID CODE VD-7013		E-134M
14+920.0, LT	BRIDGE 2 VT 279	1	150	200	0.03						1				X			X																ESIGN ID CODE VD-7013		E-134M
15+152.0, RT	BRIDGE 3 VT 279	1	150	200	0.03						1				X			X																ESIGN ID CODE VD-7013		E-134M
15+192.0, LT	BRIDGE 3 VT 279	1	150	200	0.03						1				X			X																ESIGN ID CODE VD-7013		E-134M
15+930.0, RT	Bennington College NEXT RIGHT	1	5400	2700		14.58					2																	2		346.8	W200x26.6		FUSE PLATE BOLT TENSION TO BE SET AT 90 kN	TSD-1	
VT. ROUTE 279 D.P.I. 0146(1) C/4 16+767.0, RT	BRIDGE 4 VT 279	1	150	200	0.03						1				X			X																ESIGN ID CODE VD-7013		E-134M
Y10+024.0, LT	BRIDGE 4 VT 279	1	150	200	0.03						1				X			X																ESIGN ID CODE VD-7013		E-134M
												m	m	m	m 13.6	m	m		EA	kg	kg	kg		kg	kg	kg	kg								
TOTALS			m² 0.24	m² 14.58	EA.	m²						m			m 13.6					kg			EA.	kg				EA. 2	EA.	kg 346.8					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT: BENNINGTON - HOOSICK	PROJECT NO.: D.P.I. 0146(1) C/6
DESIGN FILE NAME: TSSSO1.DGN	
IPARM FILE NAME: N/A	PLOT DATE: 2/04
SURVEYED BY: N/A	SURVEY DATE: N/A
SQUAD LEADER: T.P.K.	DRAWN BY: C.A.K.
DWG. NO. TSS-1	SHEET: 45 OF 83

FILE NAME =u:\516\VAOT\CONTRACTS\TSSSO1.dgn
DATE/TIME =2/16/2004
USER =2225