STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 2.8	50 3.2	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	FOUND-ATION	TUBULAR STEEL Ø (mm) kg/m 75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	MASS	POST SIZE	SIGN REMOVED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
VT. ROUTE 279 WESTBOUND: 17+379.0, LT	BRIDGE 5-1 VT 279	1	150	200	0.03						1				X			X																ESIGN ID CODE VD-701		E-134M
17+431.0, LT	EXIT 25 M.P.H.	1	900	1200	1.08						2					X		X															ESIGN ID CODE W13-2] REMOVE FLASHING BEACONS AND INSTALL ON NEW POSTS		E-150M
17+530.3, LT	Bennington North Bennington EXIT ONLY	1	7200	4800		34.56																											OVERHEAD SIGN TO BE MOUNTED ON NEW STEEL CANTILEVER SIGN STRUCTURE	TSD-1	
17+602.3, LT	2790 0202 0340	1	150	250	0.04						1				X			X															ESIGN ID CODE VD-700]		E-138M
17+615.0, RT		1	900	900	0.81						1						X	X															ESIGN ID CODE R3-4]		E-143M
17+670.0 LT		1	600	600	0.36																													SECTION 3	
17+670.0, LT	Bennington North Bennington ½ MILE	1	7200	4500		32.40					3																		3	1188.2	W310x44.5		FUSE PLATE BOLT TENSION TO BE SET AT 146 kN	TSD-1	
17+670.0 LT		1	600	600	0.36																													SECTION 3	
~~17+730.0, LT~~	~~SPEED LIMIT 50~~	~~1~~	~~900~~	~~1200~~	~~1.08~~						~~1~~									~~10.5~~													ESIGN ID CODE R2-1] INSTALLED, LATER REMOVED		E-142M
17+670.0 LT		1	600	600	0.36																													SECTION 3	
17+808.0, LT	WEST	1	750	375	0.28						2						X	X															ESIGN ID CODE M3-2]		E-136BM
	VERMONT 279	1	1125	900	1.01																												ESIGN ID CODE M1-5]		E-136BM
	BRIDGE 6-1 VT 279	1	150	200	0.03																												ESIGN ID CODE VD-700		E-134M
												m	m	m	m 3.4	m 11.1	m 16.2		EA	kg 10.5	kg	kg		kg	kg	kg	kg								
TOTALS					m^2 4.36	m^2 66.96	EA.	m^2				m			m 30.7					kg 10.5			EA.	kg				EA.	EA. 3	kg 1188.2					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT: BENNINGTON - HOOSICK	PROJECT NO.: D.P.I. 0146(1) C/6
DESIGN FILE NAME: TSS501.DGN	
IPARM FILE NAME: N/A	PLOT DATE: 2/04
SURVEYED BY: N/A	SURVEY DATE: N/A
SQUAD LEADER: T.P.K.	DRAWN BY: C.A.K.
DWG. NO. TSS-2	SHEET: 46 OF 83

FILE NAME =u:\5116\vaos\contract6\tss01.dgn
DATE/TIME =2/18/2004
USER =2225