STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

MAST Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NO. OF POSTS	NEW SIGN POSTS: FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) kg/m 44 2.8	50 3.2	63 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) kg/m 75 1.9	100 2.5	100 MOD 2.5	TUBULAR STEEL Ø (mm) FOUNDATION	75 11.3	89 13.4	100 16.1	125 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	MASS	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
VT. ROUTE 279 WESTBOUND: 17+916.0, LT	BRIDGE 14'-4" VT 279	1	150	200	0.03						1				X			X																ESIGN ID CODE VD-701		E-134M
	279 0202 0360	1	150	250	0.04																												ESIGN ID CODE VD-700		E-138M
17+972.9, RT	ONE WAY	1	900	300	0.27						2					X		X																ESIGN ID CODE R6-1R1		E-142M
18+200.0, LT		1	1200	1200	1.44						2						X	X															ESIGN ID CODE W4-3		E-155M
AB 10+140 LT	← BENNINGTON COLLEGE 1	1	1800	250	0.45																												INSTALLED ON EXISTING POSTS	SECTION 15	
CD 10+130 LT	← BENNINGTON COLLEGE 1	1	1800	250	0.45																												INSTALLED ON EXISTING POSTS	SECTION 15	
AB 10+140 LT	←	2	100	120																													SHEET ALUMINUM FOR OVERLAY	SECTION 14	
CD 10+130 LT	←	2	100	120																													SHEET ALUMINUM FOR OVERLAY	SECTION 14	
17+903 OH	BENNINGTON DOWNTOWN	1	4050	750																													SHEET ALUMINUM FOR OVERLAY	SECTION 10	
61+201.4	VERMONT 279 WEST TROY ↗	1	3600	1950		7.02																											SB ON 67A @ 279 WB ON RAMP INSTALLED ON EXISTING SUPPORTS	SECTION 6	
US 7 NB @ NORTHSIDE DR	VERMONT 279	1	900	1250																													OVERHEAD SIGN SHEET ALUMINUM FOR OVERLAY	SECTION 11	
US 7 NB @ VT 279	VERMONT 279	1	900	1250																													OVERHEAD SIGN SHEET ALUMINUM FOR OVERLAY	SECTION 12	
US 7 SB @ EXIT 10H	VERMONT 279	1	900	1250																													OVERHEAD SIGN SHEET ALUMINUM FOR OVERLAY	SECTION 13	
US 7 SB JUST NORTH OF EXIT 1	VERMONT 279	1	900	1250																													(TO VT 279 NEXT EXIT) SIGN SHEET ALUMINUM FOR OVERLAY	SECTION 9	
US 7 SB JUST NORTH OF EXIT 1	NEXT EXIT	1	2750	460																													(TO VT 279 NEXT EXIT) SIGN SHEET ALUMINUM FOR OVERLAY	SECTION 9	
												m	m	m	m 1.7	m 8.0	m 12.6		EA	kg	kg	kg		kg	kg	kg	kg								
												m			m 22.3					kg			EA.	kg				EA.	EA.	kg					
					m² 1.78	m²	EA.	m²																														

TOTALS

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT: BENNINGTON - HOOSICK

PROJECT NO.: D.P.J. 0146(1) C/6

DESIGN FILE NAME: TSSS01.DGN
#PARM FILE NAME: N/A
SURVEYED BY: N/A
SQUAD LEADER: T.P.K.
DWG. NO. TSS-3

PLOT DATE: 2/04
SURVEY DATE: N/A
DRAWN BY: C.A.K.
SHEET: 47 OF 83

FILE NAME = u:\SIGS\VAOT\CONTRACT6\TSSS01.dgn
DATE/TIME = 2/16/2024
USER = 2229