STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

Metric

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (mm)	HEIGHT (mm)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL kg/m 1.7	3.0	4.5	SQUARE STEEL (mm) 44 kg/m 2.8	50 kg/m 3.2	63 kg/m 5.0	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (mm) 75 kg/m 1.9	100 kg/m 2.5	100 MOD kg/m 2.5	TUBULAR STEEL Ø (mm) FOUND-ATION	75 kg/m 11.3	89 kg/m 13.4	100 kg/m 16.3	125 kg/m 21.7	W-SHAPE STEEL FTG. SIZE 600 mm	750 mm	MASS	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
RAMPS: E2+230.0 RT		1	1200	1200	1.44						2					X		X															[SIGN ID CODE W4-6]	TSD-1	
E2+434.4, RT		1	900	900	0.81						1						X	X															[SIGN ID CODE R3-2]		E-143M
E2+065.0		1	900	1200	1.08						1									4.38														SECTION 21	
E2+055.0, RT		1	900	1200	1.08						1									10.5													[SIGN ID CODE W13-2]		E-150M
E2+097.0, RT		1	750	375	0.28						1						X	X															[SIGN ID CODE M4-5]		E-136AM
		1	750	375	0.28																												[SIGN ID CODE M3-3]		E-136AM
		1	900	900	0.81																												[SIGN ID CODE M1-4]		E-136AM
	SHEET SUBTOTAL				4.70	-									-	11.6	9.7			10.5								-	-	-					
	DWG. NO. TSS-1 SUBTOTAL				0.24	14.58									13.6	-	-			-								2	-	346.8					
	DWG. NO. TSS-2 SUBTOTAL				4.36	66.96									3.4	11.1	16.2			10.5								-	3	188.2					
	DWG. NO. TSS-3 SUBTOTAL				1.78	-									1.7	8.0	12.6			-								-	-	-					
	DWG. NO. TSS-4 SUBTOTAL				5.66	-									6.8	16.0	15.8			10.5								-	-	-					
RTE 7 NB & KOCHER DR		1	600	300	0.18																												INSTALLED ON EXISTING POSTS	SECTION 4	
		1	750	600	0.45																												INSTALLED ON EXISTING POSTS	SECTION 4	
WEIGH STATION GATE 12+800		2	1830	210	0.38																												INSTALLED ON EXISTING GATE	SECTION 20	
RTE 7 SB @ EXIT 1		1	6000	3750		22.5																											INSTALLED ON EXISTING SUPPORTS	SECTION 8	
		1	1890	750		1.42																												SECTION 8	
												m	m	m	m 25.5	m 46.7	m 54.3		EA	kg 31.5	kg	kg		kg	kg	kg	kg								
TOTALS					m^2 16.74	m^2 81.54	EA.	m^2				m			m 126.5					kg 31.5			EA.	kg				EA. 2	EA. 3	kg 1535					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT: BENNINGTON - HOOSICK	PROJECT NO.: D.P.I. 0146(1) C/6
DESIGN FILE NAME: TSSSOI.DGN	
IPARM FILE NAME: N/A	PLOT DATE: 2/04
SURVEYED BY: N/A	SURVEY DATE: N/A
SQUAD LEADER: T.P.K.	DRAWN BY: C.A.K.
DWG. NO. TSS-5	SHEET: 49 OF 83

FILE NAME =d:\5:16\VAGT\CONTRACT6\TSSS01.dgn
DATE/TIME =2/16/2004
USER =2225