QUANTITY SHEET

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

EROSION CONTROL	FULL E & C ITEMS	LANDSCAPE		QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
		100		100	HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	EST.
		40		40	HR	TRUCK RENTAL (N.A.B.I.)	608.37	EST.
		40		40	HR	LOADER RENTAL, TYPE I (N.A.B.I.)	608.40	EST.
		1250		1250	MGA	DUST CONTROL WITH WATER (MOD)	609.10	EST.
		300		300	HR	UNIFORMED TRAFFIC OFFICER	630.10	EST.
		600		600	HR	FLAGGERS	630.15	EST.
	1			1	LS	FIELD OFFICE-ENGINEERS	631.10	-
	1			1	LU	FIELD OFFICE-TELEPHONE (N.A.B.I.)	631.25	-
		1		1	LS	MOBILIZATION	635.10	-
		1		1	LS	TRAFFIC CONTROL	641.10	-
2000				2000	SY	GEOTEXTILE FOR SILT FENCE	649.51	EST.
80				80	LB	SEED	651.15	EST.
30				30	LB	SEED-(WINTER RYE)	651.17	EST.
250				250	LB	FERTILIZER	651.18	EST.
		285		285	LB	FERTILIZER (MOD)- (MYCORRHIZAL PRODUCT)	651.18	EST.
1				1	TON	AGRICULTURAL LIMESTONE	651.20	EST.
1				1	TON	HAY MULCH	651.25	EST.
		50		50	EA	HAY BALES FOR EROSION CONTROL (MOD)	651.26	EST.
		40		40	CY	CEDAR BARK MULCH (MOD)	651.27	EST.
		320		320	CY	TOPSOIL	651.35	EST.
		50		50	CY	TOPSOIL (MOD)	651.35	EST.
50				50	SY	EROSION MATTING (JUTE)	654.10	EST.
		10		10	EA	EVERGREEN SEEDLINGS (WHITE PINE- 1.0-2.0' MINIMUM HT, 1-GALLON CONTAINER)	656.15	-
		11		11	EA	EVERGREEN TREES (WHITE PINE- 5.0-6.0' MINIMUM HT, CONTAINER/ B&B)	656.20	-
		36		36	EA	DECIDUOUS TREES (DOWNY SERVICEBERRY- 5.0-6.0' MINIMUM HT, CONTAINER/ B&B)	656.30	-
		2		2	EA	DECIDUOUS TREES (RED MAPLE- 1.5-2.0" CAL, B&B)	656.30	-
		6		6	EA	DECIDUOUS TREES (SUGAR MAPLE- 1.5-2.0" CAL, B&B)	656.30	-
		13		13	EA	DECIDUOUS TREES (PAPER BIRCH-CLUMP- 8.0-10.0' MINIMUM HT, CONTAINER/ B&B)	656.30	-
		5		5	EA	DECIDUOUS TREES (WHITE ASH-1.5-2.0" CAL, B&B)	656.30	-
		22		22	EA	DECIDUOUS TREES (GREEN ASH- 1.5-2.0'" CAL, B&B)	656.30	-
		40		40	EA	DECIDUOUS TREES (NORTHERN RED OAK- 1.5-2.0" CAL, B&B)	656.30	-
		222		222	EA	DECIDUOUS TREES (GRAY BIRCH- 3.0-4.0' MINIMUM HT, 1-GALLON CONTAINER)	656.30	-
		134		134	EA	DECIDUOUS TREES (WHITE ASH- 3.0-4.0' MINIMUM HT, 1-GALLON CONTAINER)	656.30	-

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		ALL PURPOSE EXCAVATOR RENTAL, TYPE I (SEE NOTE SHEET 4B)
48	HR	EXCAVATION/ PLANTING PURPOSES
32	HR	SCARIFYING COMPACTED SOILS
20	HR	ROUND
100	HR	TOTAL
		DUST CONTROL WITH WATER(MOD)
1000	MGA	FIRST PLANTING, TOTAL JOB
41	MGA	SECOND PLANTING, 135 TREES ONLY
209	MGA	ROUND, 20% OF FIRST AND SECOND PLANTINGS
1250	HR	TOTAL
		TOPSOIL
80	CY	DESIGN QUANTITY
240	CY	EXTRA QUANTITY* SEE LAYOUT SHEETS
320	HR	TOTAL

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

SHEET NAME: QUANTITY SHEET
PROJECT NAME: SEARSBURG-WILMINGTON
PROJECT NUMBER: NHF 010-1(18) C-1

FILE NAME: 78d096/design/landq.dgn
PROJECT LEADER: J. BROWN
DESIGNED BY: J. Brown
IPARM FILE NAME: landq01.i

PLOT DATE: 21-JAN-2004
DRAWN BY: SQAUD B
CHECKED BY: SQUAD B
SHEET 5 OF 30