LANDSCAPE SUMMARY SHEET

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SHEET	SEGMENT	STATION BEGIN	STATION END	OFFSET POSIT.		EVERGREEN SEEDLING PST-TR		EVERGREEN TREE PST	DECIDUOUS TREE AA	AR	AS	BP	FA	FP	QR		BPO-TR	FA-TR	OR-TR	PT-TR		DECIDUOUS SHRUBS AI	CS	RA	RR	RT	SP	VL		AM	CA	CR	SD		GRND CVR HF	REMARKS
LAND01	US ROUTE 9																																		
SH. 7																																			
			SHEET 7	TOTAL		0		0	0	0	0	0	0	0	0		0	0	0	0		0	0	0	0	0	0	0		0	0	0	0		0	
LAND02	US ROUTE 9																																		
SH. 8	EMBANKMENT	113+50	114+50	LT	X2												4	4	4	8			36				36				44				
	TREES	113+25	114+25	RT										3																					
	TREES	120+75	121+25	LT										3																					
	SHRUB BED	120+50	122+00	LT																		20				100									
			SHEET 8	TOTAL		0		0	0	0	0	0	0	6	0		4	4	4	8		20	36	0	0	100	36	0		0	44	0	0		0	
LAND03	US ROUTE 9																																		
SH. 9																																			
	TREES	127+50	128+25	LT										3																					
	TREES	128+25	128+50	LT							2																								
	TREES	128+75	129+50	LT											7																				
	TREES	133+50	134+50	LT													20																		
	SHRUB BED	135+00	135+50	LT																						40									
	SHRUB BED	128+25	128+75	LT																						80									
	SHRUB BED	130+25	130+75	RT																			40												
	SHRUB BED	131+00	131+50	RT													10					10	10								10				
	TREES	133+50	134+00	RT													20																		
			SHEET 9	TOTAL		0		0	0	0	2	0	0	3	7		50	0	0	0		10	50	0	0	120	0	0		0	10	0	0		0	
LAND04	US ROUTE 9																																		
SH. 10	SHRUB BED	140+50	141+00	LT																						40									
	EMBANKMENT	141+50	142+00	LT	X1												2	2	2	4			18				18				22				
	TREES	144+50	145+00	LT													10																		
	SHRUB BED	142+25	142+75	RT																		40													
	SHRUB BED	145+00	145+50	RT																						20									
			SHEET 10	TOTAL		0		0	0	0	0	0	0	0	0		12	2	2	4		40	18	0	0	60	18	0		0	22	0	0		0	
LAND05	US ROUTE 9																																		
SH. 11	SHRUB BED	156+00	156+50	RT																		20								12					
			SHEET 11	TOTAL		0		0	0	0	0	0	0	0	0		0	0	0	0		20	0	0	0	0	0	0		0	12	0	0		0	
LAND06	US ROUTE 9																																		
SH. 12	SHRUB BED	156+50	158+00	RT																		60								30					
			SHEET 12	TOTAL		0		0	0	0	0	0	0	0	0		0	0	0	0		60	0	0	0	0	0	0		0	30	0	0		0	
LAND07	US ROUTE 9																																		
SH. 13																																			
	TREES	176+25	177+00	LT								3																							
	TREES	179+00	180+10	LT											4																				
			SHEET 13	TOTAL		0		0	0	0	0	3	0	0	4		0	0	0	0		0	0	0	0	0	0	0		0	0	0	0		0	

SHEET NAME:	LANDSCAPE SUMMARY SHEET 1
PROJECT NAME:	SEARSBURG - WILMINGTON
PROJECT NUMBER:	NHF 010-1(18) C-1

FILE NAME: 78d096/design/landq.dgn	PLOT DATE: 21-JAN-2004
PROJECT LEADER: J. BROWN	DRAWN BY: SQUAD B
DESIGNED BY: J. Brown	CHECKED BY: SQUAD B
IPARM FILE NAME: lands01.i	SHEET 28 OF 30