STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	2.0 2.16	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	TUBULAR STEEL Ø (in) FOUNDATION	lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
											OPTION ITEMS																									
EXIT 7 RAMP A STA. 1+26.86 RT	NORTH VERMONT 2A	1	24	12	2.00						2												2	212.8 LBS								X	M3-1		E-136B
		1	24	24	4.00																			X										E-136B
		1	21	15	2.19																			14/14									M6-1	E-136B
	EAST VERMONT 289	1	24	12	2.00																												M3-2	E-136B
		1	30	24	5.00																													E-136B
		1	21	15	2.19																												M6-3	E-136B
	SOUTH VERMONT 2A	1	24	12	2.00																												M3-3	E-136B
		1	24	24	4.00																													E-136B
		1	21	15	2.19																												M6-1	E-136B
EXIT 7 RAMP A STA. 1+13.97 RT	NORTH VERMONT 2A	1	24	12	2.00						2																					X	M3-1		E-136B
		1	24	24	4.00									X		X																		E-136B
		1	21	15	2.19									16/16																			M6-3	E-136B
	EAST VERMONT 289	1	24	12	2.00																												M3-2	E-136B
		1	30	24	5.00																													E-136B
		1	21	15	2.19																												M6-1	E-136B
EXIT 7 RAMP A STA. 2+33.69 RT	RAMP 30 M.P.H.	1	36	48	12.00						2			X 14/14		X																	W13-3		E-150
EXIT 7 RAMP A STA. 3+35.76 RT	PROHIBITED PEDESTRIANS HITCHHIKERS STOPPING FOR HITCHHIKERS BICYCLES SCHOOL FARM MACHINERY SNOW VEHICLES	1	36	36	9.00						2			X 14/14		X																	VR-046		E-142
EXIT 7 RAMP A STA. 9+75.32 LT - STA. 12+40.14 LT		4	30	36	30.00						4			X 14/14		X 14/14																	W1-8		E-150
EXIT 7 RAMP A STA. 12+59.31 LT AND RT	WRONG WAY	2	36	24	12.00						4			X 14/14		X 14/14																	R5-1A		E-143
EXIT 7 RAMP A STA. 13+83.10 LT - STA. 17+20.51 LT		5	30	36	37.50						5			X 14/14		X 14/14																	W1-8		E-150
EXIT 7 RAMP A STA. 14+32.07 RT	2890 0406 0780	1	6	10	0.42						1	X 8'			X 14/14																				E-138
EXIT 7 RAMP A STA. 17+44.25 RT		1	30	30	6.25						1			X 14'		X																	R3-2		E-143
EXIT 7 RAMP A STA. 19+08.67 RT	7A 0247 0786	1	6	10	0.42						1	X 8'			X																				E-138
EXIT 7 RAMP D STA. 19+07.09 LT	DO NOT ENTER ONE WAY ONE WAY	1	30	30	6.25						1			X 14'		X																	R5-1		E-143
		1	36	12	3.00																												R6-1R		E-142
		1	36	12	3.00																												R6-1R		E-142
												FT 16.00	FT	FT 315.00	FT 16.00	FT 315.00	FT		EA	LB	LB	LB		LB 228	LB	LB	LB								
TOTALS		SF 162.79	SF	EA.	SF							FT 331.00 ~~331.00~~ 314.00			FT 331.00					LB			EA. 2	LB ~~228~~ 212.8				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET 1

PROJECT NAME: ESSEX
PROJECT NUMBER: NH 2403 (I)S

FILE NAME: pave/04b032/p04b032.dgn
PROJECT LEADER: EPD
DESIGNED BY: JDA
PLOT FILE: p04b032ssl.i

PLOT DATE: 23-APR-2009 15:5
DRAWN BY: SJB, RHB
CHECKED BY: EPD
SHEET 24 OF 48