STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.0 lb/ft 2.16	SQUARE STEEL (in) 2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) 3.0 lb/ft 1.3	TUBULAR ALUMINUM Ø (in) 4.0 lb/ft 1.7	TUBULAR ALUMINUM Ø (in) 4.0 MOD lb/ft 1.7	TUBULAR STEEL Ø (in) FOUNDATION	TUBULAR STEEL Ø (in) 3.0 lb/ft 7.6	TUBULAR STEEL Ø (in) 3.5 lb/ft 9.0	TUBULAR STEEL Ø (in) 4.0 lb/ft 10.8	TUBULAR STEEL Ø (in) 5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
OPTION ITEMS																																					
EXIT 7 RAMP D STA. 18+94.74 RT	DO NOT ENTER	1	30	30	6.25						2			X 16/16		X																X	R5-1 BACK TO BACK		E-143
	SOUTH VERMONT 2A	1 1 1	24 24 21	12 24 15	2.00 4.00 2.19																												M3-3 M6-1		E-136B E-136B E-136B
	NORTH VERMONT 2A	1 1 1	24 24 21	12 24 15	2.00 4.00 2.19																												M3-1 M6-1		E-136B E-136B E-136B
EXIT 7 RAMP D STA. 17+97.37 RT	ONLY ONLY	1	36	30	7.50						2			X 14/14		X																	VR-925		E-145A
EXIT 7 RAMP D STA. 16+72.57 LT	WRONG WAY	1	36	24	6.00						2			X 14/14		X																	R5-1A		E-143
EXIT 7 RAMP D STA. 16+72.57 RT	WRONG WAY	1	36	24	6.00						2			X 14/14		X																	R5-1A		E-143
EXIT 7 RAMP D STA. 16+00.00 RT	COLCHESTER → ← ESSEX JUNCTION						2				2			X 14/14		X																			
EXIT 7 RAMP D STA. 11+41.67 RT		1	36	36	9.00						2			X 14/14		X																	W3-3		E-152
EXIT 7 RAMP D STA. 8+04.39 RT	2890 0406 0780	1	6	10	0.42						1	X 8'				X																			
EXIT 7 RAMP D STA. 5+15.70 LT - STA. 6+55.54 LT		3	30	36	22.50						3			X 12/12/12		X																	WI-8		E-150
EXIT 7 RAMP D STA. 5+09.40 LT	EXIT 7	1	72	60		30.00					2													2	X 190 LBS 12.5/12.5									E-131
EXIT 7 RAMP D STA. 5+01.69 LT		1	18	18	2.25						1			X 8'		X																	OMI-1		E-150
STA. 419+99.80 RT	EAST VERMONT 289	1 1	~~30~~ 24 45	~~15~~ 12 36	3.13 11.25						2			X 16/16		X																	M3-2		E-136B
STA. 421+78.62 LT	ALL TRAFFIC MUST EXIT	1	36	36	9.00						2			X 16/16		X																		43	
												FT 8.00	FT	FT ~~300.00~~ 280.00	FT 8.00	FT 300.00	FT		EA	LB	LB	LB		LB 228	LB	LB	LB								
TOTALS			SF 99.68	SF 30.00	EA. 2	SF						FT ~~308.00~~ 288.00			FT 308.00					LB			EA. 2	LB ~~228~~ 190				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET 2

PROJECT NAME: ESSEX
PROJECT NUMBER: NH 2403 (I)S

FILE NAME: pave/04b032/p04b032.dgn
PROJECT LEADER: EPD
DESIGNED BY: JDA
PLOT FILE: p04b032ss2.i

PLOT DATE: 23-APR-2009 15:5
DRAWN BY: SJB, RHB
CHECKED BY: EPD
SHEET 25 OF 48