STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.0 lb/ft 2.16	SQUARE STEEL (in) 2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) 3.0 lb/ft 1.3	TUBULAR ALUMINUM Ø (in) 4.0 lb/ft 1.7	TUBULAR ALUMINUM Ø (in) 4.0 MOD lb/ft 1.7	TUBULAR STEEL Ø (in) FOUND-ATION	TUBULAR STEEL Ø (in) 3.0 lb/ft 7.6	TUBULAR STEEL Ø (in) 3.5 lb/ft 9.0	TUBULAR STEEL Ø (in) 4.0 lb/ft 10.8	TUBULAR STEEL Ø (in) 5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
														OPTION ITEMS																							
EXIT 9 RAMP D STA. 2+30.61 RT		1	36	36	4.50						2			X 16/16		X																	RI-2		E-146
EXIT 9 RAMP D STA. 4+14.56 RT	PROHIBITED PEDESTRIANS BICYCLES STOPPING FOR HITCHHIKERS ANIMALS SLOW TRAFFIC FARM MACHINERY SNOW VEHICLES	1	36	36	9.00						2			X 14/14		X																	VR-046		E-142
EXIT 9 RAMP D STA. 12+77.19 RT	DO NOT ENTER	1	30	30	6.25						1			X		X																	R9-1 BACK TO BACK		E-143
		1	30	30	6.25									14																			R3-2		E-143
EXIT 9 RAMP A STA. 5+09.60 LT		1	18	18	2.25						1			X 8		X																	OMI-1		E-150
EXIT 9 RAMP A STA. 5+89.51 LT	EXIT 9	1	72	60		30.00					2												2	12/12.25= 184.3 lbs X											E-131
EXIT 9 RAMP A STA. 7+03.53 RT		1	36	36	9.00						2			X 14/14		X																	W3-3		E-152
EXIT 9 RAMP A STA. 9+09.05 RT	ESSEX JUNCTION 1 ➔ ⬅ 1 ESSEX	1	72	12	6.00						2			X 14/14		X																	DI-1		E-123
		1	72	12	6.00																												DI-1		E-123
EXIT 9 RAMP A STA. 11+11.08 RT	EAST VERMONT 15	1	24	12	2.00																												M3-2		E-136B
		1	24	24	4.00						2			X 16/16		X																X			E-136B
		1	21	15	2.19																												M6-1		E-136B
	WEST VERMONT 15	1	24	12	2.00																												M3-4		E-136B
		1	24	24	4.00																															E-136B
		1	21	15	2.19																												M6-2R		E-136B
EXIT 9 RAMP A STA. 11+60.43 LT&RT	WRONG WAY	2	36	24	12.00						4			14/14 X 14/14		X																	R5-1A		E-143
EXIT 9 RAMP A STA. 14+30.76 RT	STOP DO NOT ENTER	1	30	30	6.25						1			X		X																	R1-1 BACK TO BACK		E-143
		1	30	30	6.25									14																			R5-1		E-143
	ONE WAY ONE WAY	1	36	12	3.00																												R6-1L BACK TO BACK		E-142
		1	36	12	3.00																												R6-1R		E-142
												FT	FT	FT 255.00 240.00	FT	FT 255.00	FT		EA	LB	LB	LB		LB 228 184.3	LB	LB	LB							
TOTALS					SF 96.13 95.53	SF 30.00	EA.	SF				FT 255.00 240.00			FT 255.00					LB			EA. 2		LB 228 184.3			EA.	EA.	LB				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET 7

PROJECT NAME: ESSEX
PROJECT NUMBER: NH 2403 (1)S

FILE NAME: pave/04b032/p04b032.dgn
PROJECT LEADER: EPD
DESIGNED BY: JDA
PLOT FILE: p04b032ss7.i

PLOT DATE: 23-APR-2009 15:5
DRAWN BY: SJB, RHB
CHECKED BY: EPD
SHEET 30 OF 48