STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	2.0 2.16	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	TUBULAR STEEL Ø (in) FOUND-ATION	lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																									
STA. 528+00.00 LT AND RT	MILE 10	2	12	36	6.00						2		X 10/10		X																		DIO-2		E-139
STA. 527+90.00	VT 15 VT 2A 1/4 2	1	168	84		98.00																											MOUNTED ON OVERHEAD BRIDGE	43	
STA. 529+98.34 RT		1	36	36	9.00						2			X 16/16		X																	W4-1		E-150
STA. 533+03.83 LT	EMERGENCY STOPPING ONLY	1	30	24	5.00						1			X 14		X																	R8-7		E-142
EXIT 10 RAMP B STA. 2+62.81 RT		1	36	36	4.50						2			X 14/14		X																	RI-2		E-146
EXIT 10 RAMP B STA. 4+63.15 RT	PROHIBITED PEDESTRIANS BICYCLES EQUESTRIANS MOTORIZED ANIMALS BICYCLES FARM MACHINERY SNOW VEHICLES	1	36	36	9.00						2			X 14/14		X																	VR-046		E-142
EXIT 10 RAMP B STA. 10+43.10 RT	DEAD END / ONE WAY	1 1	30 30	30 30	6.25 6.25						1			X 14		X																	R5-1 BACK TO BACK R3-2		E-143 E-143
EXIT 10 RAMP C STA. 2+25.00 LT		1	18	18	2.25						1			X					1														OMI-1 SLEEVE REQUIRED - FLANGED CHANNEL SIGN POST FOR THIS ASSEMBLY IS MODIFIED TO INCLUDED THE COST OF THE SLEEVE.		E-150
EXIT 10 RAMP C STA. 3+71.17 LT		1	18	18	2.25						1			X 8		X																	OMI-1		E-150
EXIT 10 RAMP C STA. 4+18.64 LT	EXIT 10	1	72	60		30.00					2											2	12.5/13= 193.8lbs X											
EXIT 10 RAMP C STA. 5+41.54 RT		1	36	36	9.00						2			X 14/14		X																	W3-3		E-152
EXIT 10 RAMP C STA. 9+29.91 LT&RT	WRONG WAY	2	36	24	12.00						4			14/14 X 14/14		X																	R5-1A		E-143
EXIT 10 RAMP C STA. 10+37.17 RT	AHEAD	1 1	36 30	36 12	9.00 2.50						2			X 16/16		X																	W11-1 R3-17A		E-153B E-143B
EXIT 10 RAMP C STA. 11+37.35 LT		1	18	18	2.25						1			X 8		X																	OMI-1		E-150
												FT	FT	FT	FT	FT	FT		EA	LB	LB	LB		LB	LB	LB	LB								
													16.00 15.00 (MOD.)	270.00	16.00	270.00							228											
TOTALS		SF 85.25	SF 128.00	EA.	SF		FT ~~286.00~~ 268.00 15.00 (MOD.)				FT 286.00				LB			EA. 2	LB ~~228~~ 193.8				EA.	EA.	LB										

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET 9

PROJECT NAME: ESSEX
PROJECT NUMBER: NH 2403 (I)S

FILE NAME: pave/04b032/p04b032.dgn
PROJECT LEADER: EPD
DESIGNED BY: JDA
PLOT FILE: p04b032ss9.i

PLOT DATE: 23-APR-2009 15:5
DRAWN BY: SJB, RHB
CHECKED BY: EPD
SHEET 32 OF 48