STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	2.0 2.16	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	TUBULAR STEEL Ø (in) FOUNDATION	lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																								
EXIT 10 RAMP C STA. 11+62.64 LT	DO NOT ENTER; ONE WAY; ONE WAY	1 1 1	30 36 36	30 12 12	6.25 3.00 3.00						1			X 14		X																R5-1 R6-1R BACK TO BACK R6-1R		E-143 E-142 E-142
EXIT 10 RAMP C STA. 11+86.41 LT	DO NOT ENTER; ONE WAY; ONE WAY	1 1 1	30 36 36	30 12 12	6.25 3.00 3.00						1			X 14		X																R5-1 R6-1R BACK TO BACK R6-1R		E-143 E-142 E-142
EXIT 10 RAMP C STA. 12+37.72 LT	DO NOT ENTER	1	30	30	6.25						1			X 14		X																R5-1		E-143
EXIT 10 RAMP C STA. 12+41.54 RT	DO NOT ENTER;	1 1	30 36	30 36	6.25 ~~4.50~~ 3.90						2			X 14/14		X																R5-1 BACK TO BACK R1-2		E-143 E-146
	ONE WAY; ONE WAY	1 1	36 36	12 12	3.00 3.00																											R6-1L R6-1R		E-142 E-142
EXIT 10 RAMP C STA. 12+76.00 RT		1	36	36	9.00						2			X 14/14		X																W6-1		E-151
EXIT 10 RAMP D STA. 1+69.25 LT		1	18	18	2.25						1			X 8		X																OM1-1		E-150
EXIT 10 RAMP D STA. 3+48.24 RT		1	36	36	~~4.50~~ 3.90						2			X 14/14		X																RI-2		E-146
EXIT 10 RAMP D STA. 4+30.91 RT	PROHIBITED PEDESTRIANS BICYCLES STOPPED VEHICLES ANIMALS BICYCLES FARM MACHINERY SLOW VEHICLES	1	36	36	9.00						2			X 14/14		X																VR-046		E-142
EXIT 10 RAMP D STA. 9+26.97 RT	DO NOT ENTER	1 1	30 30	30 30	6.25 6.25						1			X 14		X																R3-2 BACK TO BACK R5-1		E-143 E-143
EXIT 10 RAMP A STA. 3+93.45 LT		1	18	18	2.25						1			X 8		X																OM1-1		E-150
EXIT 10 RAMP A STA. 4+17.05 RT		1	36	36	9.00						2			X 16/16		X																W3-3		E-152
EXIT 10 RAMP A STA. 4+40.48 LT	EXIT 10	1	72	60		30.00					2											2	X 13/13= 197.6lbs											E-131
EXIT 10 RAMP A STA. 7+21.59 LT&RT	WRONG WAY	2	36	24	12.00						4			X		X																R5-1A		E-143
EXIT 10 RAMP A STA. 8+19.18 RT	AHEAD	1 1	36 30	36 12	9.00 2.50						2			X		X																W11-1 R3-17A		E-153B E-143B
												FT	FT	FT ~~330.00~~	FT	FT 330.00	FT		EA	LB	LB	LB		LB 228	LB	LB	LB							
TOTALS			SF ~~119.50~~ 118.3	SF 30.00	EA.	SF			FT ~~330.00~~ 300.00			FT 330.00			LB			EA. 2		LB ~~228~~ 197.6				EA.	EA.	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET 10

PROJECT NAME: ESSEX
PROJECT NUMBER: NH 2403 (1)S

FILE NAME: pave/04b032/p04b032.dgn
PROJECT LEADER: EPD
DESIGNED BY: JDA
PLOT FILE: p04b032ss10.1

PLOT DATE: 23-APR-2009 15:5
DRAWN BY: SJB, RHB
CHECKED BY: EPD
SHEET 33 OF 48